
APPENDIX C TRAFFIC VOLUMES ALONG COUNTY ROADS, US FOREST SERVICE ROADS, AND BUREAU OF LAND MANAGEMENT ROADS



SOUTHWAT IN DOMESTICATION

US FOREST SERVICE ROADS

The US Forest Service currently has jurisdiction over 1,658 miles of differing types of roads in Umatilla County. Most of them are located in the Umatilla and Wallowa-Whitman National Forests and are made of gravel in the rural areas. The primary function of these roads is to provide access for logging trucks and recreational vehicles to all the different parts of the forest lands.

The Forest Service is not a public road agency; therefore, responsibilities and liabilities are not the same as those of the county and state. Road closures in some areas may be imminent with continuing reductions in federal budgets. Priority routes are determined by recreational and commercial uses.

Maintenance Levels

The Forest Service utilizes five different maintenance levels which are operational and objective in nature. These levels are identified as follows:

- Maintenance Level 1 Assigned to intermittent service roads during the time they are closed to vehicular traffic. The closure period must exceed one year. Basic custodial maintenance is performed to keep damage to adjacent resources to an acceptable level and to perpetuate the road to facilitate future management activities. Emphasis is normally given to maintaining drainage facilities and runoff patterns. Planned road deterioration may occur at this level. Appropriate traffic management strategies are "prohibit" and "eliminate."
- Maintenance Level 2 Assigned to roads open for use by high clearance vehicles. Passenger car traffic is not a consideration. Traffic is normally minor, usually consisting of one or a combination of administrative, permitted, dispersed recreation, or other specified uses. Log haul may occur at this level. Appropriate traffic management strategies are either to (1) discourage or prohibit passenger cars or (2) accept or discourage high clearance vehicles.
- Maintenance Level 3 Assigned to roads open and maintained for travel by a prudent driver in a standard passenger car. User comfort and convenience are not considered priorities. Roads in this maintenance level are typically low speed, single lane with turnouts and spot surfacing. Some roads may be fully surfaced with either native or processed material. Appropriate traffic management strategies are either "encourage" or "accept". "Discourage" or "prohibit" strategies may be employed for certain classes of vehicles or users.
- Maintenance Level 4 Assigned to roads that provide a moderate degree of user comfort and convenience at moderate travel speeds. Most roads are double lane and aggregate surfaced. However, some roads may be single lane. Some roads may be paved and/or dust abated. The most appropriate traffic management strategy is "encourage". However, the "prohibit" strategy may apply to specific classes of vehicles or users at certain times.
- Maintenance Level 5 Assigned to roads that provide a high degree of user comfort and convenience. These roads are normally double lane, paved facilities. Some may be aggregate surfaced and dust abated. The appropriate traffic management strategy is "encourage."

The distinction between Forest Service maintenance levels is not always sharply defined. Some parameters overlap two or more different maintenance levels. Maintenance levels are based on the best overall fit of the parameters for the road in question. In the situations where the parameters do not indicate a definite selection, the desired level of user comfort and convenience is used as the overriding criteria to determine the maintenance level. Forest Service road maintenance includes a variety of work activities. Activities may be either detailed and site specific, or broad and general.

Bureau of Land Management Roads

The Bureau of Land Management (BLM) has jurisdiction over 22 miles of roads within Umatilla County. This number includes eight miles of natural surface roads and seven miles of gravel roads. The seven miles of paved roadway, now abandoned, runs near the south fork of the Walla Walla River and was formerly used by Boise Cascade company for logging operations. The primary function of these roads is to provide access for logging and grazing on BLM lands. The BLM is not a public road agency; therefore, responsibilities and liabilities are not the same as those of the county and state. Road closures in some areas may be imminent with continuing reductions in federal budgets. Priority routes are determined by commercial uses. Currently, all BLM roads in Umatilla County are subject to an annual visual inspection. Maintenance is usually performed only in the case of washouts due to storms.

US Forest Service Roads

Traffic volumes on Forest Service roads are intermittent and can range from 0 to 100 vpd or more.

Bureau of Land Management Roads

Traffic volumes of BLM roads are very low, usually under 10 vpd. This number will increase when a log haul is in progress.

UmaTula County TSP part of Exhibit B



Access Management Standards

Access Management Spacing Standards

The following tables show the access spacing standards for the access management classifications listed in Goal 3, Policy 3A: Classification and Spacing Criteria, Action 3A.1.

INTERCHANGE SPACING®								
Ascess Management Classification	å res	Anterchange Siracung©						
Interstate* and Non-Interstate	Urban	3 miles (5 kilometers)						
Freeways (NHS)	Rural	6 miles (10 kilometers)						
All Expressways on Statewide	Urban	1.9 miles (3 kilometers)						
(NHS), Regional and District Highways	Rural	3 miles (5 kilometers)						

Table 12: Interchange spacing

Notes for Table 12:

- * Interstate interchange spacing must be in conformance with federal policy.
- ① The spacing standards in Table 12 are for planning and design of new interchanges on freeways or expressways. A major deviation study is required to change these standards, but the deviation should consider the spacing requirements in the Interchange Access Management Area Tables 16-19.
- ② Crossroad to crossroad centerline distance.

Appendicos

	SPACING ST	ANDARDS F	OR STATEWID	E HIGHWA	YS®	
	Rur	al ·		- L'rhar	ı.	
Posted Speed®	Lypiessway.	Other	Expressway	Otter	UBA	STA.
≥55	5280	1320	2640	1320		
50	5280	1100	2640	1100		
40 & 45	5280	990	2640	990		
30 &c 35		770		770	720	4
≤25		550		550	520	4)

Table 13: Access management spacing standards for statewide highways (measurement is in feet)*

Notes for Table 13:

Note: The numbers in circles (2) refer to explanatory notes that follow tables.

- * Measurement of the approach road spacing is from center to center on the same side of the roadway.
- ** Spacing for Expressway at-grade intersections only. See Table 12 for interchange spacing.

	SPACING STA	NDARDS F	OR REGIONAL	HIGHWAYS	S(I)(2)	
	Rura			Urban		
Posted Speed®	Expressway	Other	Expressway ##	Other	URA	SIA
≥55	5280	990	2640	990		
50	5280	830	2640	830		
40 & 45	5280	750	2640	750		
30 & 35		600		600	425	(
≤25		450		450	350	•

Table 14: Access management spacing standards for regional highways (measurement is in feet)*

Notes for Table 14:

Note: The numbers in circles (②) refer to explanatory notes that follow tables.

- * Measurement of the approach road spacing is from center to center on the same side of the roadway.
- ** Spacing for Expressway at-grade intersections only. See Table 12 for interchange spacing.

Appendices

	SPACING STANDARDS FOR DISTRICT HIGHWAYS®										
	Ruta			Erban							
Posted Speed®	Expressway	Other	Expressway ##	Otjet	UBA	SIA					
≥55	5280	700	2640	700							
50	5280	550	2640	550							
40 & 45	5280	500	2640	500							
30 & 35	·	400		400	350	4					
≤25		400		400	350	4					

Table 15: Access management spacing standards for district highways (measurement is in feet)*

Notes for Table 15:

Note: The numbers in circles (2) refer to explanatory notes that follow tables.

- * Measurement of the approach road spacing is from center to center on the same side of the roadway.
- ** Spacing for Expressway at-grade intersections only. See Table 12 for interchange spacing.

Appendices

Notes on Tables 13, 14 and 15:

① Where a right of access exists, access will be allowed to a property at less than the designated spacing standard only if that property does not have reasonable access and the designated spacing cannot be accomplished. If possible, other options should be considered such as joint access.

Where the right of access exists, the number of approach toads (driveways) to a single property shall be limited to one, even when the property frontage exceeds the spacing standards. More than one approach road may be considered if, in the judgment of the Region Access Management Engineer, additional approach roads are necessary to accommodate and service the traffic to a property, and additional approach roads will not interfere with driver expectancy and the safety of the through traffic on the highway.

Approach roads shall be located where they do not create undue interference or hazard to the free movement of normal highway or pedestrian traffic. Locations on sharp curves, steep grades, areas of restricted sight distance or at points which interfere with the placement and proper functioning of traffic control signs, signals, lighting or other devices that affect traffic operation will not be permitted.

If a property becomes landlocked (no reasonable access exists) because an approach road cannot be safely constructed and operated, and all other alternatives have been explored and rejected, ODOT might be required to purchase the property. (Note: If a hardship is self-inflicted, such as by partitioning or subdividing a property, ODOT does not have responsibility for purchasing the property.)

(Note 1) has precedence over notes 2, 3 and 4.)

- These standards are for unsignalized access points only. Signal spacing standards supersede spacing standards for approaches.
- ① Posted (or Desirable) Speed: Posted speed can only be adjusted (up or down) after a speed study is conducted and that study determines the correct posted speed to be different than the current posted speed. In cases where actual speeds are suspected to be much higher than posted speeds, ODOT reserves the right to adjust the access spacing accordingly. A determination can be made to go to longer spacing standards as appropriate for a higher speed. A speed study will need to be conducted to determine the correct speed.
- Minimum spacing for public road approaches is either the existing city block spacing or the city block spacing as identified in the local comprehensive plan. Public road connections are preferred over private driveways, and in STAs driveways are discouraged. However, where driveways are allowed and where land use patterns permit, the minimum spacing for driveways is 175 feet (55 meters) or mid-block if the current city block spacing is less than 350 feet (110 meters).

Appendices

Access Management Spacing Standards for Interchanges

The following tables show the access spacing standards for interchanges as discussed in Goal 3, Policy 3C: Interchange Access Management Areas.

STANDA	STANDARDS FOR FREEWAY INTERCHANGES WITH TWO-LANE CROSSROADS									
Category of			SpacingD	imersion						
Mainine	dyp∈ofAxe≇	A	X	Y	<u>Z</u>					
7. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1.	Fully Developed	1 mi.	750 ft.	1320 ft.	750 ft.					
	Urban	(1.6 km)	(230 m)	(400 m)	(230 m)					
FREEWAY	Urban	1 mi-	1320 ft.	1320 ft.	990 ft.					
FREEWAI	Uroan	(1.6 km)	(400 m)	(400 m)	(<u>300 m</u>)					
	D1	2 mi-	1320 ft.	1320 ft.	1320 ft.					
	Rural	(3.2 km)	(400 m)	(400 m)	(400 m)					

Table 16: Minimum spacing standards applicable to freeway interchanges with two-lane crossroads

Notes for Table 16:

- If the crossroad is a state highway, these distances may be superseded by the Access Management Spacing Standards, providing the distances are greater than the distances listed in the above table.
- No four-legged intersections may be placed between ramp terminals and the first major intersection.
- A = Distance between the start and end of tapers of adjacent interchanges
- X = Distance to the first approach on the right, right in/right out only
- Y = Distance to first major intersection; no left turns allowed in this roadway section
- Z = Distance between the last right in/right out approach road and the start of the taper for the on-ramp




Figure 18: Measurement of spacing standards for table 16

STANDARDS	FOR FREEWAY INTE	RCHANGES	WITH MULTI	-LANE CROSS	ROADS	
			Spaci	og Dimens	οπ	Market Street
Category of Mainline	Lype of Area	Α	\mathbf{X}	Ϋ́	<u> Z</u>	M
	Fully Developed	1 mi.	750 ft.	1320 ft.	990 ft.	1320 ft.
	Urban	(1.6 km)	(230 m)	(400 m)_	(300 m)_	(400 m)
FREEWAY	11.4	1 mi.	1320 ft.	1320 ft.	1320 ft.	1320 ft.
IRELWIXI	Urban	(1.6 km)	(400 m)	(400 m)	(400 m)	(400 m)
	D 1	2 mi.	1320 ft.	1320 ft.	1320 ft.	1320 ft.
	Rural	(3.2 km)	(400 m)	(400 m)	(400 m)	(400 m)

Table 17: Minimum spacing standards applicable to freeway interchanges with multi-lane crossroads

Notes for Table 17:

- If the crossroad is a state highway, these distances may be superseded by the Access Management Spacing Standards, providing the distances are greater than the distances listed in the above table.
- 2. No four-legged intersections may be placed between ramp terminals and the first major intersection.
- A = Distance between the start and end of tapers of adjacent interchanges
- X = Distance to first approach on the right, right in/right out only
- Y = Distance to first major intersection
- Z = Distance between the last approach road and the start of the uper for the on-ramp
- M = Distance to first directional median opening. No full median openings are allowed in nontraversible medians to the first major intersection




Figure 19: Measurement of spacing standards for table 17

Appendices

CTAN	STANDARDS FOR NON-FREEWAY INTERCHANGES WITH TWO-LANE CROSSROADS										
		Speed of	\$4K*11404401W7\Y\QX\X\YQ\X\XX	Spac	ing Dimen	sien					
Category of Mambiae		Mainline		C	X	<u> </u>	Z				
The state of the s	Fully	45 mph	2640 ft.	1 mi.	750 ft.	1320 ft	750 ft.				
	Developed	(70 kph)	(800 m)	(1.6 km)	(230 m)	(400 m)	(230 m)				
	Urban			1 mi.	1320 ft.	1320 ft	990 ft				
EXPRESSWAY	Urban	45 mph	2640 ft.			(400 m)	(300 m) '				
		(70 kph)	(800 m)	(1.6 km)	(400 m)						
		55 mph (90	1 mi	2 mi.	1320 ft.	1320 ft.	1320 ft. !				
	Rural	kph)	(1.6 km)	(3.2 km)	(400 m)	(400 m)	(400 m)				
		<u> </u>	<u></u>			- L	a waish				

Table 18: Minimum spacing standards applicable to non-freeway interchanges with two-lane crossroads

Notes for Table 18:

- If the crossroad is a state highway, these distances may be superseded by the Access Management Spacing Standards, providing
 the distances are greater than the distances listed in the above table.
- 2. No four-legged intersections may be placed between tamp terminals and the first major intersection.
- 3. Use four-lane crossroad standards for urban and suburban locations that are likely to be widened.
- 4. No at-grade intersections are permitted between interchanges less than 5 miles apart.
- B = Distance between the start and end of tapers
- C = Distance between nearest at-grade and ramp terminal intersections or the end/start of the taper section
- X = Distance to first approach on the right; right in/right out only
- Y = Distance to first major intersection
- Z = Distance between the last right in/right out approach road and the start of the taper for the on-ramp




Figure 20: Measurement of spacing standards for table 18

STANI	STANDARDS FOR NON-FREEWAY INTERCHANGES WITH MULTI-LANE CROSSROADS											
Category of		Speed of		Contract J. M. D. W. Contractor	pacing Di							
Manline	Area	Mainline	\mathbf{B}	<u>C</u>	X	N	Z _{ive}	<u>M</u>				
	Fully	45 mph	2640 ft.	1 mi	750 ft.	1320 ft.	990 ft.	1320 ft.				
	Developed Urban	(70 kph)	(800 m)	(1.6 km)	(230 m)	(400 m)	(300 m)	(400 m)				
EXPRESSWAY		45 mph	2640 ft.	1 mi	1320 ft.	1320 ft.	1320 ft.	1320 ft.				
	Urban	(70 kph)	(800 m)	(1.6 km)	(400 m)	(400 m)	(400 m)	(400 m)				
		55 mph	1 mi.	2 mi.	1320 ft.	1320 ft.	1320 ft.	1320 ft.				
	Rural	(90 kph)	(1.6 km)	(3.2 km)	(400 m)	(400 m)	(400 <u>m</u>)	(400 m)				

Table 19: Minimum spacing standards applicable to non-freeway interchanges with multi-lane crossroads

Notes for Table 19:

- If the crossroad is a state highway, these distances may be superseded by the Access Management Spacing Standards, providing
 the distances are greater than the distances listed in the above table.
- 2. No four-legged intersections may be placed between ramp terminals and the first major intersection.
- 3. No at-grade intersections are permitted between interchanges less than 5 miles apart.
- B = Distance between the start and end of tapers
- C = Distance between nearest at-grade and ramp terminal intersections or the end/start of the taper section
- X = Distance to first approach on the right; right in/right out only
- Y = Distance to first major intersection
- Z = Distance between the last approach road and the start of the taper for the on-ramp
- M = Distance to first directional median opening. No full median openings are allowed in nontraversible medians to the first major intersection




Figure 21: Measurement of spacing standards for table 19

Appendices

Access Management Spacing Standard Minor Deviation Limits

The following tables show the access management spacing standard minor deviation limits for the access management classifications listed in Goal 3, Policy 3A: Classification Spacing Criteria, Action 3A.1. The Access Management Spacing Standards are shown in Tables 13, 14 and 15 of this Appendix. Minor deviations may be considered down to the deviation limits shown in Tables 20, 21 and 22. Any request to deviate beyond these limits is considered a major deviation.

	SPACING MIN	OR DEVIATION	V LIMITS FOR STA	TEWIDE HIGH	WAYS ①②	U Germann in Chiafach (Chiafan in na)
	Rura	The Land of the Control of the Contr		114	p 2 11	
Posted Speed@	Espressways	Other	Expressways	Other	UBA	ŠTA
\	(none)	(950)	(none)	(870)		
≥55	[none]	[1150]	[none]	[1000]		
-0	(none)	(700)	(none)	(640)		
50	[none]	[900]	[none]	[810]	,,,,	
	(none)	(560)	(none)	(530)		
40 & 45	[none]	[810]	[none]	[740]		
á2.2 ar		(400)		(350)	(350)	4
30 & 35		[675]		[600]	[600]	
	-	(280)		(250)	(250)	(4)
≤25		[525]		[400]	[400]	

Table 20: Access management spacing standard minor deviation limits for statewide highways (measurement is in feet)*

Notes for Table 20:

Note: The numbers in circles (2) refer to explanatory notes that follow the tables.

- * Measurement of the approach road spacing is from center to center on the same side of the roadway.
- ** Spacing for Expressway at-grade intersections only. See Table 12 for interchange spacing.
- (____) = Driveway spacing minor deviation limit.
- [___] = Public street spacing minor deviation limit.

Appendices

	SPACING MIN	OR DEVIATION	N LIMITS FOR REG	IONAL HIGHV	VAYS D@	
	, ikiid			Ucb		
LPosted Speed	Expressivevs	Ωther	Expressways	Other	L BA	STA
(.003) 440 Parale (17 103)	(nonc)	(700)	(none)	(700)		
≥55	[none]	[870]	[none]	[870]		
4.0	(none)	(540)	(none)	(540)		
50	[none]	[640]	[none]	[640]		
40 & 45	(none)	(460)	(none)	(460)		
40 & 45	[none]	[550]	[none]	[550]		
		(300)		(300)	(300)	(4)
30 & 35		[375]		[375]	[375]	
		(220)		(220)	(220)	(4)
≤25		[350]		[350]	[350]	

REGION FIVE

Table 21: Access management spacing standard minor deviation limits for regional highways (measurement is in feet)*

Notes for Table 21:

Note: The numbers in circles (②) refer to explanatory notes that follow the tables.

- * Measurement of the approach road spacing is from center to center on the same side of the roadway.
- ** Spacing for Expressway at-grade intersections only. See Table 12 for interchange spacing.
- (____) = Driveway spacing minor deviation limit.
- [___] = Public street spacing minor deviation limit.

Appendices

SPACING MIN	OR DEVIATIO	N LIMITS FOR DIS	TRICT HIGHW	7AYS DQ	
CONTRACTOR OF THE PARTY OF THE			Urb		- Walland Daniel
Ecpresswaye	-Ollier	Expressvays	Other	UEA	SIA
(none)	(650)	(none)	(650)		
	[660]	[none]	[660]		
(none)	(475)	(none)	(475)		
[none]	[525]	[nonc]	[525]		
	(400)	(none)	(400)		
	[475]	[none]	[475]		
			(275)	(250)	4
			[325]	[300]	
	<u> </u>		· (200)	(175)	4
			[245]	[200]	
	Rura Expressways (11 (none) [none]	Rural Expressways Other (none) (650) [none] [660] (none) (475) [none] [525] (none) (400)	Rural Expressways Sine Expressways Sine Expressways Sine Expressways Sine Expressways Sine Sine	Expressways Sine Expressways Siner Connect C	Company Comp

Table 22: Access management spacing standard minor deviation limits for district highways (measurement is in feet)*

Notes for Table 22:

Note: The numbers in circles (2) refer to explanatory notes that follow the tables.

- * Measurement of the approach road spacing is from center to center on the same side of the roadway.
- ** Spacing for Expressway at-grade intersections only. See Table 12 for interchange spacing.
- (____) = Driveway spacing minor deviation limit
- [___] = Public street spacing minor deviation limit.

Appendices

Notes on Tables 20, 21 and 22:

① Where a right of access exists, access will be allowed to a property at less than minor deviation limits only if that property does not have reasonable access and the minor deviation limits cannot be accomplished. If possible, other options should be considered, such as joint access.

Where the right of access exists, the number of approach roads (driveways) to a single property shall be limited to one, even when the property frontage exceeds the spacing standards. More than one approach road may be considered if, in the judgment of the Region Access Management Engineer, additional approach roads are necessary to accommodate and service the traffic to a Region Access Management Engineer, additional approach roads will not interfere with driver expectancy and the safety of the through traffic on the highway.

Approach roads shall be located where they do not create undue interference or hazard to the free movement of normal highway or pedestrian traffic. Locations on sharp curves, steep grades, areas of restricted sight distance or at points which interfere with the placement and proper functioning of traffic control signs, signals, lighting or other devices that affect traffic operation will not be permitted.

If a property becomes landlocked (no reasonable access exists) because an approach road cannot be safely constructed and operated, and all other alternatives have been explored and rejected, ODOT might be required to purchase the property. (Note: If a hardship is self-inflicted, such as by partitioning or subdividing a property, ODOT does not have responsibility for purchasing the property.)

(Note 1) has precedence over notes 2, 3 and 6.)

- ② These standards are for unsignalized access points only. Signal spacing standards supersede spacing standards for approaches.
- ③ Posted (or Desirable) Speed: Posted speed can only be adjusted (up or down) after a speed study is conducted and that study determines the correct posted speed to be different than the current posted speed. In cases where actual speeds are suspected to be much higher than posted speeds, ODOT reserves the right to adjust the access spacing accordingly. A determination can be made to go to longer spacing standards as appropriate for a higher speed. A speed study will need to be conducted to determine the correct speed.
- Minimum spacing for public road approaches is either the existing city block spacing on the city block spacing as identified in the local comprehensive plan. Public road connections are preferred over private driveways, and in STAs driveways are discouraged. However, where driveways are allowed and where land use patterns permit, the minimum spacing for driveways is 55 meters (175 feet), or mid-block if the current city block spacing is less than 110 meters (350 feet).