

Pendleton.

I next proceed to establish a base line on High street South of the Railroad.

Beginning at the point established on the center line of Webb and Main Streets, thence S 23° 36' E along the center line of Main Street, at 230 feet set point on the North side of Railroad Street (this street differs in width from 54' 3 7/8" at Mission to 63' 6 1/4" at Ann Street) 490' 5" center line of Railroad track, 820' center line of Bluff Street (which is 68' 5 7/8" wide at East side of Chya Street and 71' 1 1/2" wide at West side of Thompson Street) 1230' center line of Tustin Street, 1640 ft. set point at the intersection of center lines of Main and High Streets.

I next begin at the intersection of the center lines of Webb and Calvin Streets, 2350 ft. from Main Street thence S 23° 36' E. at 1640 feet set point at the intersection of the center lines of Calvin and High Streets.

I next begin at the intersection of the center lines of Webb and Clay Streets, 1570 ft. from center of Main St., thence S 23° 36' E. at 1640 ft. set point on the center lines of Clay and High Streets. Having three points now established in High Street and all visible from the same point I find them all in line by taking a sight over them with a Transit.

I next proceed to space off the streets and blocks on the High Street base line just established by beginning at the point established on Main and High Streets, thence S 66° 24' N. 40 feet set point, thence I set points at intervals of 200 feet and 60 feet alternately, at 2350 point established on Calvin and High Streets, at 5945' 3 3/8" intersect monument No. 3 on the Western boundary line of the Reserve Addition.

I next begin at the point established in Main and High Streets, thence N. 66° 24' E. 40 ft. set point, thence I set points at intervals of 200 ft. and 60 ft. alternately, at 1570 ft. point established on Clay and High Streets, at 5676' 3 3/8" intersect Eastern boundary line of the Reservation Addition.

I next proceed to establish a base line in Court Street. By reference to the recorded plat of the Townsite of Pendleton, I find that monuments have established at the intersection of the center lines of Court and Vincent Streets, and Court and Grand Streets, from which I determined the course of the Court St. base line, having found the monuments, I begin at the monument located on Court and Grand Streets and prolong the line Eastward, at 30 ft. set

and 60 ft. monuments to mark off cross streets, at 41464' 7 7/8" intersect the Webb Street base line 3156' 10 7/8" from the center of main and Webb Streets. I here measured the angle of intersection and found it to be 22° 49' which shows the course of the Court Street base line to be N. 89° 13' E. At 4153' 7 7/8" intersect monument No. 4 on East boundary line of Reserve Addition.

I next proceed to locate monuments and streets. All monuments were placed 6 inches below the surface of the ground as per instructions and on the top of all monuments on street lines a hole 1 inch in diameter and 2 inches deep was drilled and filled with Babbitt Metal upon the center of which a small hole was made to designate the exact point where the center lines of the streets crossed. Beginning at monument No. 2 on the Western boundary line of the Reserve Addition which is also the West side of Tudor Willow Street, thence N. 66° 24' E. along Webb Street base line at 3110' 7 7/8" set monument 36 x 10 1/2 x 16" marked No. 1 at intersection of center lines of Webb and Oak Streets. At 3980' 7 3/8" set monument 36" x 12" x 12" marked No. 2 at intersection of Webb and Main Streets, at 9137' 6 1/8" set monument 30" x 14" x 16" marked No. 3, at intersection of Webb and Court St. base lines.

I next begin at Mt. No. 3 on the West boundary line of the Reserve Addition, which is also the West side of Tudor Willow Street, thence N. 66° 24' E. along High Street base line, at 215' 3 3/4" cross

Center line of West Street, at 475' 3 3/4" cross
Center line of Winter Street, at 735' 3 3/4" cross
Center line of Hazel Street, at 995' 3 3/4" cross
Center line of Spruce Street, at 1255' 3 3/4" cross
Center line of Sycamore Street, at 1515' 3 3/4" cross
Center line of Cedar Street, at 1775' 3 3/4" cross
Center line of Maple Street, at 2035' 3 3/4" cross
Center line of Pine Street, at 2295' 3 3/4" cross
Center line of Walnut Street, at 2555' 3 3/4" cross
Center line of Chestnut Street, at 2815' 3 3/4" cross
Center line of Ash Street, at 3075' 3 3/4" set monument 36" x 10" x 14" marked No. 4 at intersection of center lines of High and Oak Streets.

At 3335' 3 3/4" cross center line of Star Street
At 3595' 3 3/4" cross center line of Calvin Street
At 3855' 3 3/4" cross center line of Marie Street
At 4115' 3 3/4" cross center line of Jane Street
At 4375' 3 3/4" cross center line of Ann Street
At 4635' 3 3/4" cross center line of Lelith Street
At 4895' 3 3/4" cross center line of Aura Street