

Or of lots 12 and 13, 255' 4" to S.W. corner of block thence S. 65° 10' E. 219' 0 1/2" to the S.E. corner of block thence S. 0° 47' E. 44' 7 1/8" to corner of lots 1 and 2, 94' 7 1/8" to corner of lots 2 and 3, 144' 7 1/8" to corner of lots 3 and 4, 194' 7 1/8" to corner of lots 4 and 5, 244' 7 1/8" to corner of lots 5 and 6, 294' 7 1/8" to corner of lots 6 and 7, 344' 7 1/8" to S.E. corner of block, thence S. 89° 13' N. 100' to corner of lots 7 and 8, 200' to the place of beginning.

Description of Fractional Lots

2226.82 sq. ft. Lot 1 - Begin at the S.E. corner of block thence S. 0° 47' E. 44' 7 1/8", thence S. 89° 13' N. 99' 10 1/2" thence S. 65° 10' E. 109' 5" to the place of beginning.

5000.08 sq. ft. Lot 2 - Begin at the S.E. corner of lot 1 thence S. 0° 47' E. 50', thence S. 89° 13' N. 100' thence S. 0° 47' N. 49' 11 1/2" thence S. 65° 10' E. 0' 1 1/4" thence S. 89° 13' E. 99' 10 1/2" to the place of beginning.

2764.5 sq. ft. Lot 3 - Begin at the S.W. corner of block thence S. 0° 47' E. 5' 4" thence S. 89° 13' E. 100' thence S. 0° 47' N. 49' 11 1/2" thence S. 65° 10' N. 109' 6 1/4" to the place of beginning.

Block 7

Location - Begin at the monument in Grange and Court Streets, thence S. 89° 13' E. 810', thence S. 0° 47' N. 30' to the S.W. corner of block.

Description of Block - Begin at the S.W. corner of block thence S. 0° 47' N. 50' to the corner of lots 8 and 9, 160' to corner of lots 9 and 10, 150' to corner of lots 10 and 11, 200' to corner of lots 11 and 12, 250' to corner of lots 12 and 13, 300' to corner of lots 13 and 14, 350' to S.W. corner of block, thence S. 89° 13' E. 100' to corner of lots 14 and 1, 200' to S.E. corner of block, thence S. 0° 47' E. 50' to corner of lots 1 and 2, 100' to corner of lots 2 and 3, 150' to corner of lots 3 and 4, 200' to corner of lots 4 and 5, 250' to corner of lots 5 and 6, 300' to corner of lots 6 and 7, 350' to S.E. corner of block, thence S. 89° 13' N. 100' to corner of lots 7 and 8, 200' to the place of beginning.

Block 8

Location - Begin at the monument in Grange and Court Streets, thence S. 89° 13' E. 1070' thence S. 0° 47' N. 50' to the S.W. corner of block.

Description of Block - Begin at the S.W. corner of block, thence S. 0° 47' N. 50' to the corner of lots 2 and 3, 150'

100' to corner of lots 9 and 10, 150' to corner of lots 10 and 11, 200' to corner of lots 11 and 12, 250' to corner of lots 12 and 13, 300' to corner of lots 13 and 14, 350' to S.W. corner of block thence S. 89° 13' E. 100' to corner of lots 14 and 1, 200' to S.E. corner of block, thence S. 0° 47' E. 50' to corner of lots 2 and 3, 150' to corner of lots 3 and 4, 200' to corner of lots 4 and 5, 250' to corner of lots 5 and 6, 300' to corner of lots 6 and 7, 350' to S.E. corner of block, thence S. 89° 13' N. 100' to corner of lots 7 and 8, 200' to the place of beginning.

Block 9

Location - Begin at the monument in Grange and Court Streets, thence S. 89° 13' E. 1010' thence S. 0° 47' N. 430' to the S.E. corner of block.

Description of Block

4114.2 sq. ft. One Lot No. 7 - Begin at the S.E. corner of block thence S. 0° 47' N. 60' 7 1/8" thence S. 65° 10' N. 148' 10 7/8" thence S. 89° 13' E. 135' 9 1/8" to the place of beginning.

Block 10

Location - Begin at the monument in Grange and Court Streets, thence S. 89° 13' E. 1070' thence S. 0° 47' N. 430' to S.W. corner of block.

Description of Block - Begin at the S.W. corner of block, thence S. 0° 47' N. 50' to the corner of lots 3 and 4, 87' 4 1/2" to S.W. corner of block, thence S. 65° 10' E. 219' 0 1/2" to S.E. corner of block, thence S. 0° 47' E. 126' 7 1/8" to corner of lots 1 and 2, 176' 7 1/8" to S.E. corner of block, thence S. 89° 13' N. 100' to corner of lots 2 and 3, 200' to the place of beginning.

Description of Fractional Lots

10433.52 sq. ft. Lot 1 - Begin at S.E. corner of block thence S. 0° 47' E. 126' 7 1/8" thence S. 89° 13' N. 100' thence S. 0° 47' N. 82' 0 1/4" thence S. 65° 10' E. 109' 6 1/4" to the place of beginning.

5970.5 sq. ft. Lot 4 - Begin at the S.W. corner of block thence S. 0° 47' E. 37' 4 1/2" thence S. 89° 13' E. 100' thence S. 0° 47' N. 82' 0 1/4" thence S. 65° 10' N. 109' 6 1/4" to the place of beginning.

Block 11

S + B