



NARRATIVE: The purpose of this survey is to stake a parcel being sold.

Ambrose Shea did a survey of the N 1/2, SW 1/4, Sec. 5, in 1972 (client unknown). He set the S 1/4, C-5 1/6, & C 1/4 corners in Sec 5 by single proportion between the S 1/4 sec. 8 & N 1/4 Sec. 5 which he also set (incorrectly). The R.R. Spike at the S 1/4 Sec. 5 has been used for several surveys in Sec. 8, but I decided not to use it for this survey because it was set wrong & the proportioned corner fits Powerline Rd. Better. The origin of the monuments at the south corners of Sec 5 is unknown but they have been used in many surveys & they fall in the center of Roads.

83-205-A

SURVEY FOR RE/MAX REALTY
 IN SW 1/4 Sec. 5, T4N, R2BE, W.M. UMATILLA CO., OR.

- MONUMENTS FND (000) of Record
- 1/2" Iron Rods Set Job # SB310061
- Fence 10/17/83

EDWARDS SURVEYING P.O. Box 763
 567-3336 HERMISTON, OR.

REGISTERED PROFESSIONAL LAND SURVEYOR
 G. DENNIS EDWARDS
 GIBSON
 G. DENNIS EDWARDS
 801

SCALE: 1" = 600'