



SCALE:  
1" = 100'

- MONUMENTS FOUND SET BY FRALEY 1950 ± UNLESS OTHERWISE NOTED
- 1/2" x 24" Rebar set with alum. Tag # 951
- (000) ED OF RECORD "CHART SUBDIVISION"
- (000) FR } OF RECORD FRALEY 1950 ± SURVEY
- (000) DEED B. 336, P. 188.
- x-x- FENCE LINE

**NARRATIVE:** The purpose of this survey is to stake the corners of Eugene H. Jones et ux (B. 336, P. 188) to see how his west fence line matches his deed line & the deed line of the prop. to the west (R. 194, P. 1528).  
 I found several monuments which were set by Fraley shown on a map titled "TRACTS OF LAND" with no date. I assume it was done about 1950.  
 I check Fraleys distances between his monuments by a few hundredths, but miss his tie to the E 1/4 Cor Sec 1 by 2 feet. I held Fraleys monuments for this survey because I assume that the E 1/4 cor is in a different location than it was in about 1950 when Fraley did his survey.

**REGISTERED PROFESSIONAL LAND SURVEYOR**  
*G. Dennis Edwards*  
**OREGON**  
 JULY 16, 1971  
**G. DENNIS EDWARDS**  
 951

SURVEY FOR EUGENE JONES  
 IN SE 1/4 SEC. 1, T4N, R28E, W.M.  
 UMATILLA COUNTY, OREGON  
 12/6/90 JOB# 59011072  
 EDWARDS SURVEYING P.O. BOX 763  
 567-3336 HERMISTON, OREGON

**RECEIVED BY**  
 Umatilla County Surveyor  
 Date 3-91  
 Rec'd By [Signature]  
 No. 91-23-A

91-23-A