



5N35-10/11  
15/14

FRANK R. OFNER  
REGISTERED ENGINEER  
PENDLETON OREGON

SECTIONS 10, 11, 14, & 15  
TOWNSHIP 5N, RANGE 35  
MR. C.L. STILL

4-4-50 MPB 1"=1000' CE-34-50

11/51  
10/11  
5N35-10/11

⊙ - POST - H

1064



STRANIX AND OFNER  
ENGINEERS  
PENDLETON, OREGON  
—  
PHONE 492

May 9, 1950

Mr. Frank Hayes  
County Engineer  
Umatilla County Court House  
Pendleton, Oregon

Dear Sir:

The following is an extract of the field notes taken during a survey for Mr. C.L. Still. The survey was in Section 10, Township 5 North, Range 35; however the Section corners and quarter corners that could be found were located in Sections 11, 14, and 15 of Township 5 North, Range 35 E.W.M. The Northwest corner of Section 10 Township 5 North, Range 35 E.W.M. was found to be a rock, the North quarter corner of said Section was found to be a rock, the Northeast corner was not found. The East quarter corner was found to be a rock, and a piece of charred stake. The Southeast corner was found to be a rock and the South quarter corner was not found. The Southwest corner was found to be a rock and the West quarter corner was found to be a rock. All above were Section 10, Township 5 North, Range 35 E.W.M.

In order to complete the survey it was necessary that the Sections be divided into quarters. All the quarter corners except the Southerly quarter corner having been found, the South Section line was established between the Southeast quarter and the Southwest quarter. The distance measured and quarter corner re-established at a proportional distancethen from the South quarter corner to the North quarter corner of said Section 10the line was run and from the East quarter corner to theWest quarter corner the line was run and the intersection established at the center of Section 10, Township 5 North, Range 35. As Mr. Still's property contains both of the Northwest quarter and the Southeast quarter, as well as parts of the Southwest quarter, the two quarter Sections having been established, it became necessary then to break down the Southwest quarter to quarter quarters, this was

STRANIX AND OFNER  
ENGINEERS  
PENDLETON, OREGON  
—  
PHONE 492

done by establishing the sixteenth corners at a mid-point between the West quarter corner of the center of Section. The center of Section at the South quarter corner in the Southwest corner of Section 10 and mid-way between the Southwest corner of Section 10 and the West quarter corner of Section 10. This quarter section was then sub-divided by establishing the center of the Southwest quarter by running a line between the sixteenths corners described. We then proceeded to establish the corners of Mr. Still's property as indicated on the attached Maps, see drawing No. CE 34-50 and CE 43-50. All of the property corners within the Southwest quarter were marked with an iron pin other than the legal corners.

Very truly yours,

*Frank R. Ofner*  
Frank R. Ofner

FRO:jrr