



Fnd 1/2" I.R. 1977  
Edwards Sur. for  
T.T. & W.



SCALE:  
1" = 60'

NW. Cor  
W 1/2 NE 1/4  
NE 1/4 Sec 5

**PUNKIN CENTE ROAD**

S 89° 20' 36" W BEARING BASE 1978 Edwards survey for Myrick

NE. Cor W 1/2  
NE 1/4  
NE 1/4 Sec 5

Fnd 1/2" I.R.  
1978 Edwards  
Sur. for Myrick

**NARRATIVE:** In 1975 Wayne Harris Co. provided coordinates for the NE. Cor. Sec 5 which were used for the section breakdown by many surveyors including myself, Driver, & Staebler. In a 1978 survey for Myrick I noticed that computed corner did not fit North-South fence lines & Roads. I recomputed the NE. Cor of Sec. 5 and set a 5/8" I.R. 10.49' west of Harris' computed corner.

The corner shown on the west edge of Banks Road was set by me in a 1977 survey for T.T. & W. Const. and was set using the erroneous Harris Corner. In my 1978 Myrick survey I determined that corner to be 7.64' west of the actual corner.

This survey is based on a section breakdown using my 1978 NE. Cor of Sec. 5 and the Iron Rods set fall in the North-South fences.

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*G. Dennis Edwards*

**OREGON  
JULY 18, 1971  
G. DENNIS EDWARDS  
951**

82-091-Ax

SURVEY FOR ROFF CONSTRUCTION  
IN NE 1/4 Sec 5, T4N, R29E, WM.  
UMATILLA CO. OREGON

6/21/82 (000) of record  
0 1/2" IRs Set      ● Monuments Found  
Job # 58206041

EDWARDS SURVEYING      P.O. Box 763  
567-3336      Hermiston, OR.