



NARRATIVE

The purpose of this survey was to partition off a 1.1 acre tract from that Parcel 3 belonging to Union Pacific Land Resources as described on Page 582 of Roll 9 of the Deed Records of Umatilla County, Oregon. The East one-quarter corner of Section 8 and the Southeast corner of Section 8, Township 1 South, Range 32 East, W.M. were found and used to confirm the legal description. The South line of this parcel was set one-half the distance between two existing warehouses as directed by the client. The North line was determined by extending the acreage northward between the railroad and the County Road.

Bearings are based upon the legal description for Parcel 3 on Page 582 of Roll 9 of the Deed Records of Umatilla County, Oregon.

CURVE DATA

No.	Radius	Arc	Chord	Chord Bearing
1	5579.65	412.89	412.80	$111^{\circ}58'29''E$
2	5634.65	421.40	421.31	$514^{\circ}58'29''W$

- denotes iron pipe found
- denotes 3/8in. x 30in. iron pin with aluminum cap set

David H. Krumbain

RECEIVED BY
 Umatilla County Surveyor
 Date 6-82
 Rec'd By BLS
 No. 82-48-B

Revised August 17, 1982-MAI

 KRUMBEIN ENGINEERING CO. ENGINEERS - SURVEYORS - PLANNERS 221 S. Main, Pendleton, Oregon	SCALE 1" = 50'
	DATE MAY 26, 1982
	DRN BY MAI
	CKD BY J.H.K.
Survey for PENDLETON RANCHES, INC. located in Section 8, T1S, R32E, W.M.	
DRNG NO 82-160	