

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis Edwards

OREGON
JULY 15, 1903
G. DENNIS EDWARDS
951

NARRATIVE


THE PURPOSE OF THIS SURVEY IS TO STAKE 25 PARCELS AS WERE PREVIOUSLY DESCRIBED AND PARTITIONED OUT OF THE EAST 3/4 OF THE NORTH HALF OF THE SE 1/4 OF SECTION 35.

THOMPSON SUBDIVIDED SAID SECTION 35 IN 1972 IN A CONTROL SURVEY (H-266) IN PREPARATION FOR THE "LANDOVER HILLS" SUBDIVISION SURVEY. IN 1980 MONUMENTS WERE FOUND AT THE EAST 1/4 CORNER OF THE SE CORNER OF SAID SECTION 35 WHICH DIFFER FROM THE LOCATION OF THOMPSON'S COMPUTED CORNERS. THOSE MONUMENTS WERE SET IN 1910 BY KIMBRELL AND REPLACED BY BRASS CAPS BY KRUMBEN.

I USED THOMPSON'S CENTER 1/4 CORNERS AND CS 1/6 CORNERS AND KIMBRELL'S CORNERS FOR THE E 1/4 CORNER AND THE SE CORNER OF SECTION 35.

LEGEND

- MONUMENT FOUND
- 1/2" x 24" IRON REBAR SET WITH METAL TAG #951
- ⊙ 5/8" x 30" IRON REBAR SET WITH METAL TAG #951
- BPA- CENTER LINE BPA TRANSMISSION LINE
- G- CENTER LINE NATURAL GAS LINE
- IP- CENTER LINE IRRIGATION PIPE
- I- CENTER LINE IRRIGATION DITCH
- P- POWER LINE



SCALE: 1"=200'

FIND 5/8" REBAR SET IN 1978 SURVEY FOR LEDBETTER.

SE COR SEC 35 FUD B.C. SET BY KRUMBEN IN 1980 IN PLACE OF IRON PIPE KIMBRELL SET IN 1910.

SURVEY FOR LEROY HAAGEN
IN THE SE 1/4 SEC 35 T5N, R20E.
W.M., UMATILLA COUNTY, OREGON
4/17/87
JOB # 58703013
EDWARDS SURVEYING, P.O. BOX 763
567-3336 HERMISTON, OREGON

RECORDED BY
Dennis Edwards
Date: 6-8-87
Book: 87-35-D