



LEGEND

- - SET 5/8" BY 30" IRON PIN WITH 1/2" YELLOW PLASTIC CAP MARKED "OR PLS 1106 WA PLS 17312".
- - MONUMENT FOUND AS NOTED.
- (XOX) - RECORD DIMENSIONS, RESERVE ADDITION PLAT.
- X— - EXISTING FENCE LINE.
- ① - LOT NUMBERS, BLOCK 157, RESERVE ADDITION.

NARRATIVE OF SURVEY

THIS SURVEY WAS MADE AT THE REQUEST OF TERRY WIDEL, TO LOCATE AND MONUMENT BOUNDARIES OF LOT 6, BLOCK 157, RESERVE ADDITION, PENDLETON, OREGON. CONTROLLING MONUMENTS ARE SHOWN. THE LOT PERIMETER WAS LAID OUT BY RECORD ANGLE AND DISTANCE USING RESERVE ADDITION MONUMENTS NO. 8 & 14 FOR CONTROL.

THIS SURVEY WAS MADE WITH A 2 PERSON CREW USING A LIETZ SET 3 B AUTOMATIC ONE SECOND TOTAL STATION. THE SURVEY WAS MADE BY A COMBINATION OF CLOSED TRAVERSE AND OPEN FIELD TRAVERSE WITH RADIAL TIES, WITH ANGLES AND DISTANCES DOUBLED WHEN MEASURING TO CONTROLLING CORNERS AND SETTING MONUMENTS.

RECEIVED BY
 Umatilla County Surveyors
 Date: 10-95
 Rec'd by: KK
 No. 95-166-B
 WIDEL

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR
 Will R. Wells
 OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1108
 RENEWS 6/30/96

WILLIAM R. WELLS, PLS
 357 N.E. HWY. 11
 P.O. BOX 1696
 PENDLETON, OR 97801
 PHONE: (503) 276-6362
 DATE: 8/24/95 DR. BY: WRW
 CK. BY: WRW NO: 45-303

PROJECT:
 SURVEY FOR:
 TERRY WIDEL
 OF LOT 6, BLOCK 157,
 RESERVE ADDITION,
 PENDLETON, OREGON.
 LOCATED IN THE NW 1/4 SECTION
 12, T2N, R32E, M4, UMATILLA
 COUNTY, OREGON.