



NARRATIVE OF SURVEY

THIS SURVEY WAS PERFORMED AT THE REQUEST OF ROBERTA TOWNSEND TO LOCATE AND MARK EXTERIOR BOUNDARIES OF THE E1/2 NW1/4 SE1/4 AND NW1/2 NE1/4 NW1/4 SE1/4 OF SECTION 29. CONTROLLING SECTION AND 1/4 SECTION CORNERS WERE LOCATED AND MEASURED TO DURING SURVEY NO. 93-064-C, IN JUNE, 1993.

MEASUREMENTS OBSERVED ON THIS SURVEY WERE MADE BY A COMBINATION OF CLOSED CONTROL TRAVERSE AND RADIAL TIE MEASUREMENTS WITH A SOKKIA SET 3B AUTOMATIC TOTAL STATION. BEARINGS ARE BASED ON SURVEY NO. 93-064-C.

IN SEPTEMBER OF 1998, DURING A SURVEY OF ADJOINING PROPERTY, WE DETERMINED THE DIMENSIONS SHOWN ON THE EAST LINE OF SECTION 29, ON SURVEY NO. 93-064-C, WERE INCORRECT. THE BEARINGS WERE NOT CORRECT BECAUSE OF AN ERRONEOUS TIE TO THE EAST 1/4 CORNER OF SECTION 29. WE RETIED THE EAST 1/4 CORNER, CORRECTED DIMENSIONS ON SURVEY NO. 93-064-C ON THE EAST LINE OF SECTION 29, AND MOVED MONUMENTS & LINE POSTS SET ON SURVEY NO. 94-074-B (THE ORIGINAL 1994 TOWNSEND SURVEY), TO LOCATIONS SHOWN ON THIS AMENDED SURVEY.

11-98  
 98-235-B

REGISTERED PROFESSIONAL LAND SURVEYOR

WILLIAM R. WELLS  
 OREGON  
 JULY 22, 1977  
 WILLIAM R. WELLS  
 1108  
 RENEWS 06/30/00

WILLIAM R. WELLS, PLS  
 357 N.E. HWY. 11  
 P.O. BOX 1696  
 PENDLETON, OR 97801  
 PHONE: (503) 276-6362

DATE: 09/98 DR. BY: DMT  
 CK. BY: WRW NO: 94-229

PROJECT:  
 SURVEY FOR:  
 ROBERTA TOWNSEND

AN AMENDMENT OF SURVEY  
 NUMBER 94-074-B.

LOCATED IN THE SE1/4 SECTION 29,  
 T4N, R37E, W1M, UMATILLA COUNTY,  
 OREGON.