

RECORD OF SURVEY

SMALL TRACTS ACT, TRACT 061411
LOCATED IN THE SW1/4NE1/4, SECTION 7,
T. 4 N., R. 38 E., W.M., UMATILLA COUNTY, OREGON.

LOT 1	NE1/4NW1/4	NW1/4NE1/4	NE1/4NE1/4
	C-N 1/16TH	FOREST BOUNDARY	
LOT 2	SE1/4NW1/4 (PRIVATE)	SW1/4NE1/4 (USFS)	SE1/4NE1/4
	C 1/4	TRACT 061411	
LOT 3	NE1/4SW1/4	FOREST BOUNDARY	
	SECTION 7		
LOT 4	SE1/4SW1/4	FOREST BOUNDARY	SE1/4

SURVEYOR'S CERTIFICATE & NARRATIVE

THIS SURVEY WAS MADE AT THE REQUEST OF JOHN EHART AND JACK WALLACE, OWNERS OF LAND IN THE SE1/4NW1/4, SECTION 7, T. 4 N., R. 38 E., W.M., UMATILLA COUNTY OREGON, IMMEDIATELY WEST OF TRACT 061411. THE PURPOSE OF THE SURVEY WAS TO DEFINE THE BOUNDARIES OF TRACT 061411, WHICH WILL BE ACQUIRED BY EHART/WALLACE UNDER THE SMALL TRACTS ACT.

TO MAKE THE SURVEY, I SURVEYED BETWEEN THE EXISTING CENTER 1/4 CORNER AND CENTER-NORTH 1/16TH CORNER, AND RETIRED STRUCTURES IN THE AREA OF ENCROACHMENT. THE FIELD TRAVERSE CLOSED 1 PART IN 10000 BETWEEN THE EXISTING MONUMENTS, ESTABLISHED PER UMATILLA COUNTY SURVEY NO. 88-064-B, PERFORMED BY ME FOR THE USDA, UMATILLA NATIONAL FOREST IN 1988. THE CENTER-NORTH 1/16TH CORNER MONUMENT IS SET ON SOLID ROCK AND SOME OF THE STONES HAD FALLEN AWAY FROM THE ORIGINAL ROCK MOUND. THE ROCK MOUND AT THIS CORNER WAS REBUILT. THE LINE BETWEEN MONUMENTS AT THE CENTER 1/4 AND CENTER-NORTH 1/16TH CORNER WERE HELD AS THE BASIS OF BEARING FOR THIS SURVEY, USING THE RECORD BEARING FROM UMATILLA COUNTY SURVEY NO. 88-064-B.

THE SURVEY WAS MADE WITH A THREE PERSON CREW USING A SOKKIA SET 4B FIVE SECOND TOTAL STATION AND SDR ELECTRONIC FIELD BOOK. NEW MONUMENTS AT THE CORNERS OF TRACT WERE ESTABLISHED AND MONUMENTED AS NOTED ON THIS RECORD OF SURVEY AND AS REPORTED ON LAND CORNER RECORDS FILED WITH THIS SURVEY. SIGNS AND RED PAINT RINGS WERE NOT PLACED ON BEARING TREES AT TRACT CORNERS 2 AND 3, BECAUSE OF THE PROXIMITY TO CABINS AND THE WALLA WALLA RIVER TRAIL. IT WAS NOTED THAT "POSTING" SIGNS PLACED IN THE 1988 SURVEY ARE FULL OF BULLET HOLES.

I, WILLIAM R. WELLS, A REGISTERED LAND SURVEYOR IN THE STATE OF OREGON, DO HEREBY CERTIFY THAT THIS PLAT OF SMALL TRACT 061411, SURVEYED UNDER P.L. 97-465, AND THE CORNER RECORDS FILED SEPARATELY, ARE A CORRECT REPRESENTATION OF THE SURVEY PERFORMED BY ME DURING THE MONTH OF AUGUST, 2001.

Will. R. Wells
WILLIAM R. WELLS, PLS
Sept. 25, 2001
DATE

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106
RENEWS 6/30/02

VICINITY MAP
SECTION 7, T. 4 N., R. 38 E.,
WILLAMETTE MERIDIAN
UMATILLA COUNTY, OREGON

SCALE: 1"=600 FEET

LEGEND

- ⊕ - FOUND 2 1/2" ALUMINUM CAP ON 2 1/2" ALUMINUM PIPE, ESTABLISHED ON UMATILLA COUNTY SURVEY NO. 88-064-B.
- - SET 2 1/2" ALUMINUM CAP ON 2 1/2" BY 30" ALUMINUM PIPE, ON THIS SURVEY. CORNER RECORD FILED WITH THIS SURVEY.
- [XOX] - RECORD DIMENSION, UMATILLA COUNTY SURVEY NO. 88-064-B.

9-01
KK
01-149-B
WALLAMAP

EXAMINED AND ACCEPTED FOR THE U.S. FOREST SERVICE
THIS 25th DAY OF September, 2001.

Travis A. Selman
NATIONAL FOREST SURVEYOR

EXAMINED AND ACCEPTED FOR THE U.S. FOREST SERVICE
THIS 25th DAY OF September, 2001.

Will. R. Wells
NATIONAL FOREST SUPERVISOR

WILLIAM R. WELLS, PLS
357 N.E. HWY. 11
P.O. BOX 1696
PENDLETON, OR 97801
PHONE: (541) 276-6362

PROJECT:
EHART/WALLACE SURVEY
SMALL TRACTS ACT
TRACT 061411

DATE: 08/01 DR. BY: WRW
CK BY: WRW NO: 01-771

LOCATED IN THE SW1/4NE1/4
SECTION 7, T. 4 N., R. 38 E., W.M.,
UMATILLA COUNTY, OREGON.

