


**SURVEYOR'S NARRATIVE:**

THE PURPOSE OF THIS SURVEY IS TO STAKE THE FOUR CORNERS OF LOTS 10 AND 11, BLOCK 6, "NEWPORT ADDITION" SO A NEW FENCE CAN BE BUILT. THIS PROPERTY IS DESCRIBED IN A DEED TO LESLIE FEINBERG ON REEL 133, PAGE 1675, UMATILLA COUNTY DEED RECORDS. I USED MONUMENT TO THE EAST AND WEST OF THIS TRACT TO ESTABLISH THE SOUTH CORNERS. I COULD FIND NO MONUMENTS TO THE NORTH SO USED CONCRETE CURBS ON THE SOUTH LINES OF LOTS 4 AND 5, BLOCK 1, FOR THE BEST EVIDENCE OF LOT CORNERS TO RETRACE THE 1908 PLAT OF "NEWPORT ADDITION". I USED A TOPCON HIPER+ G.P.S. IN REAL TIME TO CONDUCT THIS SURVEY.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
9 5 1  
RENEWS 12/31/2009



- LEGEND:**
- FND. 1/2" I. REBAR ME. 1976 SUR. FOR POWELL, UNLESS NOTED OTHERWISE
  - SET 5/8"x30" IRON REBAR WITH PLASTIC CAP #951
  - ⊗ SET CONC. NAIL WITH WASHER
  - ⊛ COMPUTED LOCATION
  - [000] OF RECORD, 1908 PLAT OF "NEWPORT ADD."

SURVEY FOR LESS FEINBERG  
IN BLK 6, "NEWPORT ADD.," CITY OF HERMISTON,  
IN THE NE 1/4, SW 1/4, SEC. 11, T. 4 N.,  
R. 28 E., W.M., UMATILLA COUNTY, OREGON  
05/11/2009 JOB# 50904028  
EDWARDS SURVEYING P.O. BOX 763  
541-567-3336 HERMISTON, OREGON 97838  
DRAWN BY JMC

09-75-B

09-75-B