



- o denotes monument found
- denotes monument set as noted
- () denotes record distance

NOTES:

1. Bearings are based on a bearing of $N 63^{\circ} 18' 00'' E$ for centerline of SE 12th street.
2. Elevations are based on the i.e. of the manhole at sta. 3+43.3 as provided by the City of Milton-Freewater.
3. According to the City of Milton-Freewater
 - A. The water service at the meter is $\frac{3}{4}$ in. and served from a $1\frac{1}{2}$ in. or 2 in. line in SE 12th Street. A 12 in. main is located on the far side of South Main.
 - B. Sewer services, probably 4 in. are located at stations 2+37 and 2+74.
4. This is an old service station and it appears that the stations underground tanks are still in place.

REGISTERED PROFESSIONAL LAND SURVEYOR
 James H. Buison
 OREGON JULY 22, 1977
 JAMES H. BUISON 1087

RECEIVED BY
 Umatilla County Surveyor
 Date 5-1-80
 Rec'd By ELS
 No. R-92-B

K KRUMBEIN ENGINEERING CO. ENGINEERS - SURVEYORS - PLANNERS 221 S. Main, Pendleton, Oregon Survey and Topography for CIRCLE "K" S 50 ft. Lot 4 & Lot 5, Blk 2, Original Town of Milton, Ore.	SCALE 1" = 20'
	DATE Dec. 5, 1979
	DRN. BY MA
	CKD. BY J.H.B.
	DRNG. NO. 79-72C