



NARRATIVE OF SURVEY

LOCATION OF SURVEY

THE PARCEL SURVEYED IS THE N 1/4, NE 1/4, SE 1/4, SEC. 35, T. 2 N., R. 32 E.W.M.

METHOD & PROCEDURE OF SURVEY

RESEARCH OF THE UMATILLA COUNTY SURVEYOR'S OFFICE DISCLOSED

1. SURVEY BY USDA FOR THE MCKAY NATIONAL WILDLIFE REFUGE 1938
2. SURVEY BY KRUMBELN ENGR. CO; DRAWINGS No. 80-5D & 79-33B DATED 3/80 & 12/79 RESPECTIVELY.
3. SURVEY BY B.J. PENGRA, SURVEYOR GENERAL OF OREGON JAN. 25, 1865

THE WEST LINE OF SEC. 35 BETWEEN THE W. 1/4 COR. & NW COR. WAS USED AS THE BASIS OF BEARING FOR THIS SURVEY FOR KRUMBELN ENGR. CO. DRWG # 80-5D

THE NE COR. OF SECTION 35 WAS NOT FOUND & COULD NOT BE ESTABLISHED FROM EXISTING LANDMARKS. THE SECTION CORNERS IN EACH DIRECTION WAS THEN REFERENCED. THE CORNER COMMON TO SECTIONS 23, 24, 25 & 26 WAS NOT FOUND OR MONUMENTED. HOWEVER THE EXISTING WELL DEFINED FENCE CORNER WAS LOCATED & USED AS THE SECTION COR. THE DOUBLE PROPORTIONATE MEASUREMENT SYSTEM WAS USED TO DETERMINE THE TRUE LOCATION OF THE NE COR. OF SECTION 35. THE TRUE CORNER WAS DETERMINED TO BE 4.31 FT SW OF THE TRUE INTERSECTION OF THE SECTION LINES & FIT WELL WITH THE FENCE LINES TO THE NORTH & WEST. THE INFORMATION CONTAINED IN THE SURVEY BY THE SURVEYOR GENERAL OF ORE. DATED JAN 25, 1865 WAS USED AS THE BASIS OF THE PROPORTIONING.

THE SURVEY WAS PERFORMED BY A RANDOM CLOSED TRAVERSE WITH SIDE SHOTS UTILIZING A ONE SECOND INSTRUMENT & ELECTRONIC DISTANCE MEASURING EQUIPMENT.

THE SURVEY WAS PERFORMED IN MARCH 1982

THE SURVEY WAS PERFORMED FOR JAMES WHITNEY, PENDLETON, ORE.



GERALD L. ODMAN
 PLS #1280
 419 NW 12TH
 PENDLETON, ORE 97801
 APRIL 1982

- LEGEND
- SET BRASS CAP 12" BELOW GRD. SURFACE
 - ⊙ FL. BRASS CAP
 - () DENOTES DIST. FROM 1865 SURVEY BY SURVEYOR GENERAL OF OREGON

- REFERENCE TIES
- N. 1/4 COR. SEC. 35 : 111' SE OF TELEPHONE POLE
35.12' E. OF IP @ FENCE COR.
 - NE COR. SEC. 35 : 290' S. OF FENCE COR.
 - E. 1/4 COR. SEC. 35 : 33.6' S. OF FENCE
33.4' S. OF FENCE COR
12.5' E. OF INTERSECT. OF Co. Rd.
12.5' NE OF TELEPHONE POLE

SURVEY OF PARCEL IN SECTION 35, T. 2 N., R. 32 E.W.M.

RECEIVED BY
 Umatilla County Surveyor
 Date 6-82
 Rec'd By BLS
 No. 82-51-C