



SCALE: 1" = 20'
DATE: June 15, 1988

NARRATIVE

The purpose of this survey was to survey out a parcel of land from tax lot # 110 on map 2N32.15 as it is described in Book 322 on page 366 and in R 138 on page 760 of the Umatilla County deed records, State of Oregon. A search of the area was made and four iron pins were found as shown on this map and four iron pins were set as corner monuments as shown on this map to mark off the said parcel to encompass the house and garage containing 0.46 Acres. Point No. 2 (Pt 2) was used for control. A line was drawn and computed through Pt 2 and Pt 8 for a bearing base by using the triangle Pt 2, Pt 7 and Pt 8 with the record distances from Pt 2 to Pt 7 and Pt 7 to Pt 8 and the record bearing from Pt 2 to Pt 7 of N 50° 35' 30" E. The southeast line was placed between the garage and storage units from the County Rd. southerly to Tutuilla Creek and the south westerly line was placed along the said creek north westerly to a point on a property line common to Greclian Heights P.U.D.

NOTE:
1. It is noted herewith that the description in Book 322 on page 366 does not close by 1.41 feet north-south. no error east-west.
2. Record also means Deed.

REGISTERED PROFESSIONAL LAND SURVEYOR
DONALD L. STAEBLER
OREGON
DONALD L. STAEBLER #1333

SURVEY FOR WARREN PALMER
IN SECTION 15, T 2N, R 32E
SCALE: 1" = 20' DATE: 6-15-88
BY: DONALD L. STAEBLER
ENGINEER - SURVEYOR
1532 SW 41 ST,
PENDLETON, OREGON 97801
PH 276-7166

LEGEND

- --- set 3/4" x 30" rebar pin Marked R.L.S. 1333
- --- Found iron pin as shown size as indicated

RECEIVED BY
Umatilla County Surveyor
Date: 6-88
Rec'd by: [Signature]
No. 88-41-C