

GPS CONTROL STATION

OREGON STATE PLANE, NORTH ZONE

STATION NAME: 66	GEODETIC COOR: NAD 83(91):
SECTION: SW 1/4, S8, T.2N., R.32E., UMATILLA COUNTY, OREGON	LAT: 45° 39' 52.19734" N LONG: 118° 50' 24.98503" W
DATE SET: MARCH 1996	STATE PLANE CO-ORDINATES, NAD 83-91, INT.FT.:
SURVEYOR: WILLIAM R. WELLS PLS 1106	N: 732724.038 E: 8626393.790 THETA: 1° 10' 37.40"
FIRM: WILLIAM R. WELLS, LAND SURVEYING AND PLANNING P.O. BOX 1696 PENDLETON, OR 97801 (541) 276-6362	SCALE FACTOR: 0.99993200 ELEV: 1144.79 US.FT. ELEV. DATUM: LOCAL, CITY OF PENDLETON
ORDER: SECOND ORDER, CLASS I	CITY OF PENDLETON CO-ORDINATES INT.FT.:
	N: 48649.500 E: 34086.196

LOCATION:

TRAVEL SOUTH THEN WEST FROM MCKAY SCHOOL TO TOP OF HILL AND DIVIDE BETWEEN MCKAY AND BIRCH CREEKS. TRAVEL SOUTH ON GOOD ROAD PAST NEW HOMES THEN RIGHT AT MAILBOX AND THROUGH HOME AND FARM BUILDINGS. FOLLOW EDGE OF FIELD EAST THEN SOUTH TO BREAKS INTO UMATILLA RIVER. STATION IS EAST ACROSS DRAW ON WEST SIDE OF RIDGE TOP.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP MARKED "OR PLS 1106, WA PLS 17372".

STATION IS LOCATED ON UNFARMED SCAB LAND.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-96