

GPS CONTROL STATION

OREGON STATE PLANE, NORTH ZONE

STATION NAME: 107	GEODETIC COOR: NAD 83(91):
SECTION: SW 1/4, S22, T.2N., R.32E., UMATILLA COUNTY, OREGON	LAT: 45° 38' 16.61338" N LONG: 118° 48' 17.27936" W
DATE SET: MARCH 1996	STATE PLANE CO-ORDINATES, NAD 83-91, INT.FT.:
SURVEYOR: WILLIAM R. WELLS PLS 1106	N: 723233.349 E: 8635664.149 THETA: 1° 12' 07.96" SCALE FACTOR: 0.99992810 ELEV: 1337.91 US.FT. ELEV. DATUM: LOCAL, CITY OF PENDLETON
FIRM: WILLIAM R. WELLS, LAND SURVEYING AND PLANNING P.O. BOX 1696 PENDLETON, OR 97801 (541) 276-6362	CITY OF PENDLETON CO-ORDINATES INT.FT.:
ORDER: SECOND ORDER, CLASS I	N: 38962.043 E: 43153.031

LOCATION:

STATION BEARS SOUTH 40° EAST FROM DELAMARTER HOME. LOCATED AT EDGE OF FIELD 100 FEET M/L EAST OF NORTH-SOUTH DRAW. STATION IS LOCATED 90 FEET M/L SOUTH OF SOUTHERLY POWER TRANSMISSION LINE. EAST 1/4 CORNER OF SECTION 21 BEARS NORTH 78° WEST.

STATION IS A 5/8" X 30" IRON PIN WITH A YELLOW PLASTIC CAP MARKED "OR PLS 1106, WA PLS 17372".

STATION IS LOCATED ON A PLOWED FIREBREAK AT THE EDGE OF A CRP FIELD AND WILL BE DISTURBED WHEN FARMING RESUMES.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-96*