

GPS CONTROL STATION

OREGON STATE PLANE, NORTH ZONE

STATION NAME: 51	GEODETIC COOR: NAD 83(91):
SECTION: SE 1/4, S30, T.3N., R32E., UMATILLA COUNTY, OREGON	LAT: 45° 42' 16.12091" N LONG: 118° 50' 55.95337" W
DATE SET: MARCH 1996	STATE PLANE CO-ORDINATES, NAD 83-91, INT.FT.:
SURVEYOR: WILLIAM R. WELLS PLS 1106	N: 747253.224 E: 8623897.097 THETA: 1° 10' 15.43" SCALE FACTOR: 0.99993829 ELEV: 1450.18 US.FT. ELEV. DATUM: LOCAL, CITY OF PENDLETON
FIRM: WILLIAM R. WELLS, LAND SURVEYING AND PLANNING P.O. BOX 1696 PENDLETON, OR 97801 (541) 276-6362	CITY OF PENDLETON CO-ORDINATES INT.FT.:
ORDER: SECOND ORDER, CLASS I	N: 63230.368 E: 31899.795

LOCATION:

FROM INTERSECTION OF UMATILLA COUNTY ROADS 1100 AND 1092, GO EAST ON ROAD 1092 ONE MILE TO BEND IN ROAD. GO SOUTH ALONG AIRPORT BOUNDARY FENCE TO FENCE CORNER, STATION BEARS S 55° W, 15 FEET FROM FENCE CORNER.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP MARKED "OR PLS 1106, WA PLS 17372".

STATION IS LOCATED IN ACTIVE WHEAT FIELD AND IS SUBJECT TO DISTURBANCE.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-96