

GPS CONTROL STATION

OREGON STATE PLANE, NORTH ZONE

STATION NAME: 73	GEODETIC COOR: NAD 83(91):
SECTION: SW 1/4, S35, T.3N., R.32E., UMATILLA COUNTY, OREGON	LAT: 45° 41' 20.37658" N LONG: 118° 47' 11.56027" W
DATE SET: MARCH 1996	STATE PLANE CO-ORDINATES, NAD 83-91, INT.FT.:
SURVEYOR: WILLIAM R. WELLS PLS 1106	N: 741939.974 E: 8639937.719 THETA: 1° 12' 54.57"
FIRM: WILLIAM R. WELLS, LAND SURVEYING AND PLANNING P.O. BOX 1696 PENDLETON, OR 97801 (541) 276-6362	SCALE FACTOR: 0.99993580 ELEV: 1441.34 US.FT. ELEV. DATUM: LOCAL, CITY OF PENDLETON
ORDER: SECOND ORDER, CLASS I	CITY OF PENDLETON CO-ORDINATES INT.FT.:
	N: 57575.431 E: 47825.288

LOCATION:

FROM INTERSECTION OF JOHNS LANE AND OWENS COURT TRAVEL ALONG JOHNS LANE (GRAVEL) NORTH 1300 FEET M/L. STATION IS ON EAST SIDE OF THE ROAD. STATION IS 12 FEET NORTH OF EAST-WEST FENCE LINE. STATION IS SOUTH 65° EAST, 1320 FEET M/L FROM RADIO TOWER. STATION IS NORTH 65° EAST, 55 FEET M/L FROM BRASS CAP MONUMENT FOR SECTION CORNER TO SECTIONS 2, 3, 34, AND 35.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP MARKED "OR PLS 1106, WA PLS 17372".

STATION IS IN ACTIVELY FARMED AREA AND MAY BE DISTURBED.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-96