

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9333

QUARTER SECTION: SW

GEODETIC COOR: NAD 83(91)

SEC. 24 TWP.4 N,RGE.28E
UMATILLA CO.ORE.

LAT: 45°48'47.78170" N

DATE SET: JULY ,1993

LONG: 119°15'54.54635" W

SURVEYOR: WALTER L. CASWELL
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP
13545 NW SCIENCE PARK DR
PORTLAND, OR. 97229
(503) 643-1073

N: 785019.573 INT.FT.

E: 8516958.330 INT.FT.

THETA: 0°52'32.653"

TYPE: GPS

SCALE FACTOR: 0.999957886

ORDER: SECOND, CLASS: 1

ELEV: 642.797 US.FT.

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

FROM THE INTERSECTION OF S.W. HIGHLAND AVE. AND HWY. 395 IN HERMISTON, GO SOUTHEAST ON HWY. 395 3.0 MILE TO FEEDVILLE ROAD, THEN WEST ON FEEDVILLE ROAD 1.0 MILE TO A PAVED SIDE ROAD TO THE NORTH, THEN GO NORTH ON SIDE ROAD 0.5 MILE TO A GRAVEL SIDE ROAD TO THE EAST.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP INSCRIBED "BUFORD ASSOC. PLS 1148".

STATION IS 0.5 MILE NORTH OF INTERSECTION OF FEEDVILLE ROAD AND CROSS ROAD, AND 38 FEET EAST OF CENTERLINE OF CROSS ROAD, AND 38 FEET NORTH OF MANHOLE @ CENTERLINE OF GRAVEL ROAD.

METERS X 3.28083333333 = U.S. FEET
METERS X 3.28083989501 = INTERNATIONAL FT.

