

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9304

QUARTER SECTION: SW

GEODETIC COOR: NAD 83(91)

SEC. 10 TWP.5 N,RGE.28E
UMATILLA CO.ORE.

LAT: 45°55'37.71873" N

DATE SET: JULY ,1993

LONG: 119°17'47.58664" W

SURVEYOR: WALTER L. CASWELL
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP
13545 NW SCIENCE PARK DR
PORTLAND, OR. 97229
(503) 643-1073

N: 826417.392 INT.FT.

E: 8508334.113 INT.FT.

THETA: 0°51'12.486"

TYPE: GPS

SCALE FACTOR: 0.999982292

ORDER: SECOND, CLASS: 1

ELEV: 302.102 US.FT.

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

FROM THE INTERSECTION OF HWY. 395 (UMATILLA-STANFIELD HWY.) AND HWY. 730, TRAVEL NORTHERLY ON MCNARY DAM ACCESS ROAD 0.8 MILE ACROSS THE RAILROAD TRACKS TO A GRAVEL AREA TO THE EAST. (WEST OF FISH VIEWING AREA AT MCNARY DAM).

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP INSCRIBED "BUFORD ASSOC. PLS 1148".

STATION IS 48 FEET EAST OF THE NORTH END OF THE EAST ROAD GUARD RAIL (YELLOW), 28 FEET SOUTH AND 45 FEET WEST OF POWER POLE WITHOUT NUMBER.

METERS X 3.2808333333 = U.S. FEET
METERS X 3.28083989501 = INTERNATIONAL FT.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Walter L. Caswell

OREGON
JULY 8, 1966
WALTER L. CASWELL
737

EXP. 12/31/93