

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9305

QUARTER SECTION: NW

GEODETIC COOR: NAD 83(91)

SEC. 15 TWP.5 N,RGE.28E
UMATILLA CO.ORE.

LAT: 45°55'19.27945" N

DATE SET: JULY ,1993

LONG: 119°17'59.16858" W

SURVEYOR: WALTER L. CASWELL
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP
13545 NW SCIENCE PARK DR
PORTLAND, OR. 97229
(503) 643-1073

N: 824537.633 INT.FT.

E: 8507543.257 INT.FT.

THETA: 0°51'04.273"

TYPE: GPS

SCALE FACTOR: 0.999981108

ORDER: SECOND, CLASS: 1

ELEV: 429.628 US.FT.

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

FROM THE INTERSECTION OF HWY. 395 (UMATILLA-STANFIELD HWY.) AND
HWY. 730, TRAVEL NORTHERLY ON MCNARY DAM ACCESS ROAD 0.3 MILE TO
MONUMENT ON SOUTH RIGHT OF WAY.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP
INSCRIBED "BUFORD ASSOC. PLS 1148".

STATION IS 34 FEET SOUTH OF CENTERLINE OF ACCESS ROAD, 5 FEET
NORTH OF TOE SLOPE.

METERS X 3.2808333333 = U.S. FEET
METERS X 3.28083989501 = INTERNATIONAL FT.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Walter Caswell

OREGON
JULY 8, 1966
WALTER L. CASWELL
737

Exp. 12/31/93