

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9314

QUARTER SECTION: NE

GEODETIC COOR: NAD 83(91)

SEC. 33 TWP.5 N,RGE.28E
UMATILLA CO.ORE.

LAT: 45°52'34.94074" N

DATE SET: JULY ,1993

LONG: 119°18'25.60063" W

SURVEYOR: WALTER L. CASWELL
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP
13545 NW SCIENCE PARK DR
PORTLAND, OR. 97229
(503) 643-1073

N: 807865.429 INT.FT.

E: 8505920.664 INT.FT.

THETA: 0°50'45.527"

TYPE: GPS

SCALE FACTOR: 0.999970917

ORDER: SECOND, CLASS: 1

ELEV: 548.529 US.FT.

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

FROM THE INTERSECTION OF UMATILLA RIVER ROAD AND COONEY LANE,
TRAVEL EAST AND NORTH ON COONEY LANE TO A CROSSROAD EAST (JOY
LN.). TRAVEL EAST ON JOY LN. 0.2 MILE TO SUNSHINE, THEN NORTH ON
SUNSHINE 0.3 MILE TO TOP OF THE FIRST HILL. MONUMENT IS EAST OF
THE CENTERLINE OF SUNSHINE LANE 20 FEET.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP
INSCRIBED "BUFORD ASSOC. PLS 1148".

STATION IS 20 FEET EAST OF CENTERLINE OF SUNSHINE LANE, 2.5 FEET
WEST OF BARB WIRE FENCE, 140 FEET NORTH OF BRIDGE.

METERS X 3.28083333333 = U.S. FEET
METERS X 3.28083989501 = INTERNATIONAL FT.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Walter Caswell
OREGON
JULY 8, 1966
WALTER L. CASWELL
737

Exp. 12/31/93