

5035 J 21

TOMKINS LAND SURVEYING, INC.
20 EAST POPLAR, SUITE 204
WALLA WALLA WA 99362
PHONE: 509/522-4843
FAX 509/522-1902
email: tomkins@wwics.com

JUNE 17, 1998

HORIZONTAL CONTROL DATA

STA. NAME: 925

LOCATION: TOWNSHIP 5 NORTH, RANGE 35 EAST, WILLAMETTE MERIDIAN. S.W. 1/4 OF SECTION 12.

DESCRIPTION: 5/8" REBAR WITH A YELLOW PLASTIC CAP STAMPED "TOMKINS SURVEYING" SET AT AN ANGLE POINT IN THE SOUTHWESTERLY LINE OF THE HORIZON PROJECT PROPERTY.

GEODETIC COORDINATE: NAD 83(91)

LAT: 45°55'22.46877" N.

LONG: 118°22'36.71676" W.

STATE PLANE COORDINATE: NAD 83(91) OREGON NORTH ZONE (3601)

N: 252889.837 METERS

E: 2664671.208 METERS

N: 829691.066 INT. FEET

E: 8742359.610 INT. FEET

ELEVATION: 333.01 METERS

1092.56 FEET

ELEVATION DATUM: NAVD 88

THETA: 1°30'20.5"

GRID FACTOR: 0.999981312

SEA LEVEL FACTOR: 0.999947742

COMBINED SCALE FACTOR: 0.999929055

CONVERSION:

METERS X 3.28083333333 = U.S. FEET

METERS X 3.28083989501 = INTERNATIONAL FEET



RENEWS 12/31/99

6/17/98