

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/18/94

CORNER DESIGNATION: Z-19. South 1/4 corner Section 35, T2N., R32E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC: Most recent official GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: set a basalt stone in old mound, 12 x 12 x 10 ins., 8 ins. in the ground for 1/4 sec. cor. marked 1/4 on N. face. Dug pits, 18 x 18 x 12 ins. E. and W. of cor. 5 1/2 ft. dist. raised earth mound 1 1/2 ft. high, 3 1/2 ft. base over it. The U.S. Department of Agriculture found and accepted fence corner in 1938 and set monument. Umatilla County Survey No. H-251-B.

MONUMENT AND ACCESSORIES FOUND: 3" brass cap on iron pipe, set flush with the ground, marked as per corner detail. Set by U.S. Department of Agriculture, in 1938, Umatilla County Survey No. H-251-B.

MONUMENT MARKING DETAIL:

US DEPT AG.  
19  
R32E T2N  
S35  
1/4  
S2  
T1N  
1938  
BIOLOGICAL SURVEY

MONUMENT SET:  
Maintained Corner.

New Accessories:


Attached a witness sign to railroad tie fence corner intersection, 1.0 foot Northwest of monument.  
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 53° E-18.9 feet.  
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 88° E-18.7 feet.  
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 7° W- 15.7 feet.  
A railroad tie gate post with a brass washer stamped "PLS 1106", nailed 0.75 feet above ground, bears N 2° W- 16.3 feet.  
Attached witness corner signs to steel fence posts near each iron pin reference. Attached bearing object sign and witness sign to gate post near brass washer.

LOCATION AND COMMENTS: Corner falls in fence intersection at the East edge of McKay reservoir. Fences extend North-South and East.

COMPASS DECLINATION: 18° East  
FIRM/AGENCY: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

Surveyor's Seal

Party Chief: Robert D. English  
Notes: Robert D. English  
Witness: F. Scot Munro



renews 12-31-94