

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/14/94

CORNER DESIGNATION: Z-7. South 1/4 corner Section 32, T2N., R32E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent official GLO survey was made by David P. Thompson, under Contract No. 106, dated Aug. 16, 1864. Original notes state: set stone, 24 x 14 x 5 ins., for 1/4 sec. corner.

MONUMENT AND ACCESSORIES FOUND: Found stone 18" x 12" x 5" with visible "1/4" on face in rock jack at fence intersection.

MONUMENT MARKING DETAIL:

T2N R32E
S32
— . —
S5
T1N R32E
1994
PLS 1106

MONUMENT SET: At position of found stone, set 2 1/2" brass cap on 1 1/4" x 30" galvanized iron pipe 14" into the ground. (marked as shown in the monument detail)

New Accessories:

Set steel fence post 3.0 feet North with witness sign attached.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 31 1/2° E-28.0 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 8° E-18.9 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 76° W-23.2 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 45° W-27.0 feet.
Set steel fence posts near iron pins, with witness signs attached.
Placed bearing object signs on the iron pin reference monuments.

LOCATION & COMMENTS: Corner is located at fence intersection with fences North, South and East.

COMPASS DECLINATION: 18° East
FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Surveyor's Seal

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

PLS 1106
WILLIAM R. WELLS
1106

renewed 12-31-94