

Record of Corner Monumentation

K-15

History of original corner establishment:

N-C-1/16 corner Section 15, was monumented by C.E. Redfield during his 1919 circa. He set a 2 1/2" brass cap on a 36" pipe.

Description of corner evidence found:

I found the monument that was set by C.E. Redfield to have been torn out of the ground and the pipe bent badly, during plowing operations of the adjoining field. Monument was lying on the ground very close to the actual corner location.

Description of monument and accessories I established to perpetuate the original location of this corner:

I set a 5/8" x 36" iron pin with a 2 1/2" Brass Cap, being stamped as shown in the diagram. I drove the pin flush to the ground surface and then laid the C.E. Redfield monument along side and buried both in a mound of large stones. Monument falls in an old fence line between adjacent property owners.

Diagram:

N-C-1/16
S 15
T 1 N R 33 E
2002
ORLS 645

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James H. Hambleton

02-20-03

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

03-35-B