

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 7/26/94

CORNER DESIGNATION: Z-1, Southwest corner Section 31, T1N., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent official GLO survey was made by L.E. Wilkes, under Contract No. 29, dated Feb. 20, 1917. Notes state "Set an iron post, 3 ft. long, 2 ins. diam., 24 ins. in the ground, for witness cor. to the standard cor. of Tps. 1 N., Rs. 33 and 34 E., with brass cap (marked as shown in monument detail) and raise a mound of stone, 2 ft. base, 1 1/2 ft. high, N. of cor. This cor. is at the intersection of fences, extending N. and E."

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on 2" galvanized iron pipe protruding 14", set by Wilkes in a resurvey for the diminished reservation boundary. Witness corner is set 1 link (0.66 feet) West of corner point, listing slightly Southeast, in Southeast corner of rock corner jack. Remnants of old stone mound visible to East of monument.

MONUMENT MARKING DETAIL:

G L O
SC
T1N
R33E R34E WC
S36 | S31
T1S
1917

MONUMENT SET:

New Accessories to existing corner monument:
Attached witness sign to corner of rock jack.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 18° E-31.4 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 57° E-29.2 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 79° W-27.7 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 08° W-16.1 feet.
Attached bearing object sign to each iron pin. Set steel fence post near each iron pin with witness signs attached.
Note: Bearing objects set reference the witness corner monument, 1 LK West of true corner point.

LOCATION & COMMENTS:

Corner is located at intersection of fences extending West, East and North.

STATE PLANE CO-ORDINATE:

Oregon North, NAD 83/91, U.S. Survey Foot:
N = 679510.53
E = 8683428.85

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

RECEIVED BY
Umatilla County Surveyor
Date 2-95
Rec'd By KK
No. 95-16-C

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/96