

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Original survey and resurvey by Manius Buchanan under contract 635, 1895,

Intersect U.I.R. bdy. at C.C. established by me. The post set by me has been taken away and replaced by the former one set by Deputy Surveyor's Currin and Noland which is a Tamarack post marked UR on the W and CC on the E in a mound raised by me, from which:

A Pine 20 ins. diam. bears S60 1/2°W 86 lks. dist. marked T1N R35E S27 BT. There being no tree within limits in sec. 26, I now build a mound of stone 2 1/2 ft. base 1 1/2 ft. high E of corner.

The former witness being erroneous, I destroy the marks thereon.



Description of corner evidence found:

A sawn Ponderosa Pine stump, approx. 26" dia. rotten with scribing "27 BT" visible on open double blaze.

A mound of stone 3 ft. diam. and 1 1/2 ft. high.


Description of monument and accessories I established to perpetuate the original location of this corner:

At the corner point established along the West side of the original stone mound and at record bearing and distance from the remains of the only original bearing tree, we set a 2"x30" galvanized iron pipe, 12" in the ground to bedrock and in a mound of stone 6'x3'x1 1/2' high, with brass cap attached, marked:

From which we mark new bearing trees:

A 10" Douglas Fir, scribed "CC T1N R35E S26 BT" on a double blaze bears S55°E 52.4 ft.

And an 8" Ponderosa Pine, scribed "CC T1N R35E S27 BT" on a double blaze bears S 43°W 68.5 ft.




Attached brass washer marked "LS 1099" to lower blaze of new BT's. Bearing and horizontal distance measured to center of bearing trees at ground level.

Staff Compass (20° East Declination) Steel Tape

October 7, 1983

Witnesses: Gary Langlitz LS 1099
Dick Humiston



Office of Surveyor County of Wasco
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 11th day of November, 1983
David Krumbein by Betty Cochran
(COUNTY OFFICIAL) (DEPUTY)