


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**History of original corner establishment:**

Corner originally established by Jacob C. Cooper under GLO contract number 397, dated July 1, 1881. Surveyor General record states:  
 4 flat stones 14x14 ins laid flat ways on top of each other on steep ridge of canyon which I marked X on top and T1N S19 on NE R37E S30 on SE R36E S25 on SW and S24 on the NW angles of X from which:



A fir 18 ins diam bears S28°W, 78 lks dist marked T1N R36E S25 BT  
 No other trees within limits, too steep for pits or mounds.

Corner located by Herman D. Gradon under GLO contract number 452, dated June 16, 1882. Surveyor General record states finding the corner as per the original record of Cooper, except that Mr. Gradon calls the bearing tree a 18 inch diameter Pine--Mr. Cooper calls the bearing tree a 18 inch diameter fir.

No record of subsequent monumentation found in Umatilla County survey records.

**Description of corner evidence found:**

Found no evidence of the original corner monument.


Found a 32 inch diameter Douglas Fir S28°W, 78 lks dead and standing with blaze evident.

See map of survey dated September, 1989.

**Description of monument and accessories I established to perpetuate the**

**original location of this corner:** At record bearing and distance from the above described found original bearing tree, I set a 2½" x 30" aluminum pipe with aluminum cap marked as shown, 24 inches in the ground, from which:

**New Bearing Trees and Bearing Objects:**  
 Drove a PK nail in a 4'x3'x10' high rock outcrop approximately 3' below top and 1' West of the East edge, which bears N10°E, 18.92 feet  
 A 22 inch diameter Douglas Fir bears S2°E, 79.8 feet marked T1N R37E S30 BT  
 A 10 inch diameter Douglas Fir bears S16°W, 84.00 feet marked T1N R36E S25 BT  
 A 3' wide x 2' high rock face bears N51°W, 38.44 feet marked X BO with X on small shelf and BO on face of rock below the X.  
 Painted a 6 inch red band around all BTs and BOs.  
 Attached bearing tree and land survey monument signs to BTs.  
 Set a steel fence post approximately 5 feet North with Land Survey Monument sign attached.  
 Raised a mound of stone around monument, 4 ft. base to top of cap.



I hereby certify that the above corner point was perpetuated as hereon described on August 28, 1989.



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of the Survey Dept County of Umatilla  
 State of OR I hereby certify that the within instrument was filed in this office  
 for record on the 27th day of October 1989  
David H. Kumbier by Kathleen Kumbier  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

\*GPO-591-971, 1988

Umatilla County Surveyor  
 Date 10-89  
 Rec'd by KA