


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Timothy W. Davenport under GLO contract number 102, dated July 20, 1863. Surveyor General record states: Set gr Sec post on side of gorge made mound of rock. Corner reestablished by Herman D. Gradon under GLO contract number 452, dated June 16, 1882. Surveyor General record states: Set a basalt stone 14x12x10 ins 9 ins in the ground for ¼ sec cor marked BL ¼ on N. face and raised a mound of stone alongside. The old ¼ sec cor a post in stone mound bears W. 85 lks dist. Destroy both post and mound.

Corner perpetuated by Robert J. Chappell under BLM group no. 1184 with instructions dated Sept. 29, 1983. His notes state: The standard ¼ sec. cor. of sec. 35 T1N R36E monumented with the original basalt stone, 14x12x10 ins., firmly set, 6 ins. in the ground marked ¼ on N. face. At the corner point set an aluminum post 28 ins. long, 2½ ins. diam. 10 ins. in the ground to solid rock, and in a mound of stone 5 ft. base to top, with aluminum cap marked: (markings shown below) No suitable trees available. Deposit corner stone alongside aluminum post.




No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found a standard BLM aluminum monument marked as shown:

Monument found in a mound of stone, 5 ft. base, with 20 inches of the monument exposed.

See map of survey dated September, 1989.



Description of monument and accessories I established to perpetuate the

original location of this corner: From the found BLM corner monument:

New Bearing Objects:

A 5/8"x30" iron rebar with plastic cap marked BGA SURVEY MARKER bears N11°E, 8.90 feet
 A 5/8"x30" smooth iron pin with plastic cap marked BGA SURVEY MARKER bears N56°W, 12.85 feet.

Attached bearing tree signs to the new bearing objects.

Set a steel fencepost approximately 2 feet West with Land Survey Monument sign attached.

Rebuilt mound of stone around monument, 5 ft. base to top of cap.

I hereby certify that the above corner point was perpetuated as hereon described on August 10, 1989.

Witnesses: Rick Robinson and Craig Griffith, Jr.



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination.

Office of Survey Dept County of Umatilla
 State of OR I hereby certify that the within instrument was filed in this office
 for record on the 31 day of October 1989
David H. Rumbert by Kathleen K. Amstutz
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 10-89
 Rec'd by KA
 No. 89-101-B