


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**History of original corner establishment:**

Corner originally established by Timothy W. Davenport under GLO contract number 102, dated July 20, 1863. Surveyor General record states: Set post corner to Secs 36 & 31 Townships 1 North, Ranges 36 & 37 East from which:  
 A Hemlock 14 inch in dia bears N10°E 46 lks dist  
 A Hemlock 12 inch in dia bears N20°W 22 lks dist  
 A Hemlock 10 inch in dia bears S35°W 26 lks dist

Corner found by Jacob C. Cooper under GLO contract number 397, dated July 1, 1881, and by Herman D. Graddon under GLO contract number 452, dated June 16, 1882. Surveyor General record states finding the corner and it's accessories as per the Davenport survey.



No record of subsequent monumentation found in Umatilla County survey records.

**Description of corner evidence found:**

Found the rotted remains of the original corner post to a depth of 12 inches. The bottom 6 inches of the post has axe marks visible.

**Original Bearing Trees:**  
 A 22 inch diameter Hemlock stump bears S35°W, 26 lks  
 Tree previously opened with blaze evident. I opened and found the inside rotted with no marks visible.

Found a stump hole N20°W, 22 lks.

Found no evidence of the original Northeast bearing tree.

Distance to the original BTs are to the estimated face of blaze.

See map of survey dated September, 1989.

**Description of monument and accessories I established to perpetuate the**

**original location of this corner:** In place of the found original corner post, I set a 2½" x 30" aluminum pipe with aluminum cap marked as shown, 28 inches in the ground, from which:

**New BTs:**  
 A 13 inch diameter Western Larch bears N17°E, 47.34 feet marked T1N R37E S31 SC BT  
 A 17 inch diameter Western Larch bears N55°W, 7.87 feet marked T1N R36E S36 SC BT

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Set a steel fencepost approximately 5 feet North with land survey monument and property boundary signs attached.

I hereby certify that the above corner point was perpetuated as hereon described on August 14, 1989.

Witnesses: Rick Robinson and Jeff Petersen.



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of The Survey Dept. County of Umatilla  
 State of OR, I hereby certify that the within instrument was filed in this office for record on the 20<sup>th</sup> day of October, 1989  
David H. Lamberson by Kathleen K. Lamberson  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
 Umatilla County Surveyor

\*GPO-591-971, 1988

Date 10-89  
 Filed by KL  
 No. 89-111-B