

Index

File No. E-2

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____


T 1N R. 38E

R.D. Walla Walla County Union

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Located approximately 400 ft. east of Road 3200161.

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

Signature
Ray J. Danglez

Title
Land Surveyor

Division
PLS 1099

Headquarters

Date
12/2/80

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Corner set from survey by single proportionate measurement.
At the corner point, we set a 2"x30" Galvanized Iron Pipe,
28" in the ground, with brass cap attached, marked:

T1N R38E
S6
+
S7
W 1/16
PLS 1099
1980

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

From which we mark new BTs: An 8" Larch, scribed "W 1/16 S7 BT" on a double blaze, bears S42°E 69.8 ft. An 8" White Fir, scribed "W 1/16 S6 BT" on a double blaze bears N 70½°E 62.8 ft. Attached brass washer marked "LS 1099" to lower blaze of each BT. Placed steel fence posts approximately 5 ft. N and E of monument with signs 54-2 and 54-9 attached. Attached signs and painted BTs per Standard Specifications for Cadastral Survey, U.S.F.S., Region 6, Oct., 1979.

Work Done By Gary Langlitz Title Land Surveyor Date 12/2/80 State Registration No. PLS 1099
or Agency

Certified Cor. Record Prepared ? Yes No Filed At: Union County Surveyor Date Dec., 1980

REMARKS

Compass Declination: 20° East

Witness: David Allen