

Index

File No. E-3

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

T 1N R. 38E


R.D. Walla Walla County Union

Tract or Survey No. _____ Cor. No. _____

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

No trace remains of the original corner post or SE bearing tree. Established the true corner point at record dimensions to the only remaining ori. bearing tree, an orig. 3" now 8" yew, alive and in fair condition, with illegible scribing visible on a previously opened blaze bears N23°W 9.9 ft. from the true corner point.

PHOTO IDENTIFICATION DATA

Photo No. F16616160 1577-123

Filed At Umatilla Nat For

Object Ident. Direct

Ident. By G. Langlitz

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner located at intersection of cutting lines running N and E, approx. 200 ft. East of the end of a dirt logging road.

Gary L. Langlitz
Signature

Title
Land Surveyor

Division
PLS 1099

Headquarters

Date
8-7-80

7100-52 (3. 68)

CORNER RECORD (PERPETUATION)

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At the True Corner Point, set a 2"x30" Galvanized Iron Pipe, 24" in the ground, no rocks available for a mound, with brass cap attached, marked:

T1N R38E
 S6
 1/4 ———
 S7
 PLS 1099
 1980

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

From which we mark new BTs: An 18" Spruce, scribed "1/4 S6 BT" on a double blaze bears N89 1/2° W 57.8 ft. And a 14" Grand Fir, scribed "1/4 S7 BT" on a double blaze bears S48° E 27.6 ft. Attached brass washer, stamped "LS 1099" to lower blaze of new BTs. Placed steel fence posts 5 ft. south and 5 ft. west of monument, with signs 54-2 and 54-4 attached. Attached signs and painted BTs per Standard Specifications for Cadastral Survey, U.S.F.S. Region 6, Oct., 1979.

Work Done By: Gary Langlitz Title Land Surveyor Date 8/7/80 State Registration No. or Agency PLS 1099

Certified Cor. Record Prepared? Yes No Filed At: Union County Surveyor Date Dec., 1980

REMARKS

Compass Declination: 20° East

Witnesses: Gary Langlitz
 Tom Isaacson
 Loren Huntsman

USDA-FOREST SERVICE

Index

File No. E-3

T 1N R. 38E

Merid. Willamette

2

CORNER RECORD (SEARCH)


(Ref. FSM 7151.4)

Tract or Survey No. _____ No. _____

R.D. Pendleton County Umatilla

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

8" Yew tree 50' NW of iron fence post. Location poster Heppner Lbr. Co. saying approx. $\frac{1}{4}$ cor. blaze line 4 directions. I chopped into Yew tree and exposed scribing: $\frac{1}{4}$

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

Signature
B. Moore

Title
Eng. Tech.

Division _____

Headquarters _____

Date

7/78.

7100-52-(3/68)

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

I placed attention and bearing tree posters on the Yew and location poster on Road 1900' east.

10

Work Done By _____ Title _____ Date _____ State Registration No. or Agency _____

Certified Cor. Record Prepared ? Yes No Filed At: _____ Date _____

11

REMARKS

12

Index File No.

T.

R.

M.

Tract or Surv. No.

Cor.

13