

Index

File No.

G-3

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or


Survey No.

Cor.

No.

T. 1N R. 38ER.D. Walla Walla County UnionMerid. WillametteN.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

A steel fencepost and location poster bears approx. S26°E 40' from the monument described below. See Record Survey No. 23-1964 as filed in the office of Union County Surveyor.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is located approx. 400 ft. East of a graveled road, U.S.F.S. road No. 3200161.

Gary L. Langley
Signature

Title
Land Surveyor

Division
PLS 1099

Headquarters

Date
10-10-80

7100-52 (3. 68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

T1N R38E

Corner set from survey at intersection of straight lines between opposite exterior $\frac{1}{4}$ corners of section 7.

S7
+
C $\frac{1}{4}$

At the corner point, we set a 2"x30" galvanized iron pipe, 26" in the ground, with brass cap attached, marked:

PLS 1099
1980

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

From which we mark new BTs" A 7" Larch, scribed "c $\frac{1}{4}$ S7 BT" on a double blaze bears N54 $\frac{1}{2}$ ⁰E 13.0 ft. A 6" White Fir, scribed "c $\frac{1}{4}$ S7 BT" on a double blaze, bears N58 $\frac{1}{2}$ ⁰W 10.9 ft. Attached brass washer, marked "LS 1099" to lower blaze of each BT. Placed steel fence posts 5 ft. N and W of monument with signs 54-2 and 54-9 attached. Attached signs and painted BTs per Standard Specifications for Cadastral Survey, U.S.F.S. Region 6, Oct., 1979

Work Done By Gary Langlitz Title Land Surveyor Date 10/10/80 State Registration No. PLS 1099
or Agency

Certified Cor. Record Prepared? Yes No Filed At: Union County Surveyor Date Dec. 1980

REMARKS

Compass Declination: 18⁰ East.

Witness: John Curtiss

Index File No. G-3 T. 1N R. 38E M. Willamette Tract or Surv. No. Cor.