

**OREGON CORNER RESTORATION FORM**

Section 12 Township 3N  
County Umatilla Date: 08/20/10

Range 29E

Corner Designation: 3N29G25

1/4 Corner common to section 12, T3NR29E, and section 7, T3NR30E.

- Condition Report Only
- Not Found
- Remonumented
- Unrecorded
- Surveyed In
- Referenced Out


**Previous Renewals / Surveys, etc.**

Originally Surveyed by David P. Thompson in 1859. He set a post in a mound of earth.

**Monuments and Accessories Found: (Condition and Source)**

None

**Diagram**



Orange Magnet ●

**Sketch**

Silver Magnet ●

○ 19" Deep  
BC

Blue Magnet ●

● Pink Magnet

NAD 83/91  
OREGON STATE PLANE NORTH  
INTERNATIONAL FEET

N764541.21  
E8553804.62

LAT - 45° 45' 19.74253" N  
LON - 119° 07' 19.33746" W

**Monument (s) Set (Procedures and Description)**

Set A 1"x30" flared galvanized iron pipe with a 2 1/2" B.C. by single proportionate method.

**References Set:** "Deep One" magnets by Berntsen.  
An Orange magnet 18" deep, lies N 12°20' E, 25.02'.  
A Silver magnet 18" deep, lies N 46°20' E, 18.27'.  
A Pink magnet 18" deep, lies S 4°00' E, 18.32'.  
A Blue magnet 17" deep, lies S 69°00' W, 18.20'.

**Location and Comments**

Corner is in an active wheat field approx 1/8 mi. S of farm road, and approx 1/4 mi W of existing farm house. N of I-84.

**Compass Declination**

17° E

**Surveyors Seal**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert Douglas English*  
OREGON  
JANUARY 11, 2005  
ROBERT DOUGLAS ENGLISH  
43406LS

**RECEIVED BY:**

Date: 8-10  
Rec'd By: KK  
No. 10-140-R

**Firm / Agency**

Survey One, LLC.  
P.O. Box 382  
Pendleton, OR 97801  
(541) 276-2055

RENEWAL DATE: 12/31/09