

OREGON CORNER RESTORATION FORM

Section 13,14 Township 3N
County Umatilla Date: 05/21/10

Range 29E

Corner Designation: 3N29L21

Corner common to sections 13,14 T3NR29E.

_____	Condition Report Only
<u> X </u>	Not Found
<u> X </u>	Remonumented
_____	Unrecorded
<u> X </u>	Surveyed In
<u> X </u>	Referenced Out


Previous Renewals / Surveys, etc.

Originally Surveyed by Gates. He set a post in a mound of earth in 1859.

Monuments and Accessories Found: (Condition and Source)

None.

Diagram



Sketch

NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

Wooden Fence Post

Wooden Fence posts

N759100.36
E8548686.50

Power Pole

LAT - 45° 44' 26.89343" N
LON - 119° 08' 32.80892" W

Monument (s) Set (Procedures and Description)

A 1 1/2" x 30" galvanized iron pipe w/ a 2 1/2" brass cap, 4" below the surface, stamped as shown above. Set in fence line.

References Set:

- A Pk nail and Brass washer #43406, on a wooden fence post lies S 89° E, 5.45'.
- A Pk nail and Brass washer #43406, on a Power pole lies S 43°30' W, 6.63'.
- A Pk nail and Brass washer #43406, on a wooden fence post lies S 88°40' W, 44.17'.
- A Pk nail and Brass washer #43406, on a wooden fence post lies S 89°20' E, 22.15'.

Location and Comments

The corner is 0.5 miles South from the intersection of HWY. 320 and Coppinger Road, and West 0.5 miles.

Compass Declination
17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English
OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RECEIVED BY:

Date: 1-11
Rec'd By: KK
No. 11-14-R

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055

RENEWAL DATE: 12/31/11