

**OREGON CORNER RESTORATION FORM**

Section 21,22,27,28  
County Umatilla

Township 3N  
Date: 0/117/11

Range 29E

Corner Designation: 3N29R13

Corner common to sections 21,22,27 and 28, T3NR29E.

_____	Condition Report Only
_____X	Not Found
_____X	Remonumented
_____	Unrecorded
_____X	Surveyed In
_____X	Referenced Out


**Previous Renewals / Surveys, etc.**

Originally Surveyed by N.H. Gates in 1859. He set a post in a mound of earth.

**Monuments and Accessories Found: (Condition and Source)**

None.

**Diagram**



**Sketch**

- Orange Magnet
- Silver Magnet
- 2 1/2" B.C.  
24" Deep
- Blue Magnet
- Pink Magnet
- Crop Circle

NAD 83/91  
OREGON STATE PLANE NORTH  
INTERNATIONAL FEET

N750958.53  
E8538183.12

LAT - 45° 43' 08.23597" N  
LON - 119° 11' 02.75949" W

**Monument (s) Set (Procedures and Description)**

Set a 1"x30" galvanized iron pipe with a 2 1/2" brass cap, 24" deep, near an irrigation pivot. Stamped as shown above.

**References Set:** "Deep One" magnets by Berntsen.

- An Orange magnet 24" deep lies N 17°00' W, 30.38'.
- A Blue magnet 24" deep lies S74 °15' W, 24.27'.
- A Silver magnet 24" deep lies N 22°15' E, 23.11'.
- A Pink magnet 24" deep lies S 64°30' E, 16.61'.

**Location and Comments**

The corner is in the irrigated circle  
North of the Farm House at the Piercy  
Vineyard.

**Compass Declination**  
17° E

**Surveyors Seal**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert D. English*  
OREGON  
JANUARY 11, 2005  
ROBERT DOUGLAS ENGLISH  
43406LS

**RECEIVED BY:**

Date: 1-11  
Rec'd By: IKK  
No: 11-17-R

**Firm / Agency**

Survey One, LLC.  
P.O. Box 382  
Pendleton, OR 97801  
15411 278-2055

RENEWAL DATE: 12/31/11