

OREGON CORNER RESTORATION FORM

SECTION 20 TOWNSHIP 3N RANGE 29E R-5

COUNTY: UMATILLA DATE 8/91

CORNER DESIGNATION

SW Corner

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.


Originally surveyed by Gates in 1860 under Contract #84. He set post in mound of dirt. Staebler set a 2 1/2" B.C. on 1" Iron pipe in 1974. Co. Sur. #I-158-B.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found 2 1/2" B.C. on 1" I. pipe, badly bent, in cultivated field.

MONUMENT DETAIL

SKETCH



MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES

From which

- Center of 1321.5 ft. circle pivot Bears. N43° 23' 13" E 1801.40 ft.
- Center of 532.4 ft. circle pivot Bears. N70° 34' 08"W 199.12 feet,
- A 5/8" rebar with Alum. tag #951 Bears. N83° 31' 45"W 792.42 feet,
- A 5/8" rebar with Alum. tag #951 Bears. S77° 08' 29"E 400.35 feet.

LOCATION & COMMENTS

From Jct. of Heppner-Echo Hwy. with Echo Meadows Rd. go South on Echo Meadows Rd. 1.2miles to a chemical wash pad. then go West .5 mile to corner in a small irr. circle.

COMPASS DEC.  
FIRM EDWARDS SURVEYING  
P.O. BOX 763, HERMISTON,  
OREGON, 97838  
PARTY CHIEF D. EDWARDS  
NOTES  
WITNESS S. BENEFIT

SURVEYOR'S SEAL

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951

91-86-R