

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 3N, R 29E., W.M.

Corner Code No. T-21

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by N. H. Gates, Deputy Surveyor, under Contract No. 84, dated July 22, 1859.

The original notes state:

"Set post for 1/4 Sec. corner in mound of Earth & @ as per instructions."

DIAGRAM

T3N R29E
1/4
S261S25
1992
PLS 1106

Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Long standing fence with fences extending South and West. After confirming corner location by survey, I accept the fence corner as the best remaining evidence of the original corner location and remonument the corner point as indicated below.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set a 2 1/2" Brass cap on a 1 1/4" by 30" G.I.P. 24" in ground and surrounded with a mound of earth, from which:

- A 5/8" by 30" rebar bears S 89 1/4°W - 15.71 feet, with a Bearing Object sign nailed to nearby railroad tie.
- A 5/8" by 30" rebar bears S 89 1/4°W - 69.72 feet.
- A 5/8" by 30" rebar bears S 0 1/4°E - 26.92 feet.
- A 5/8" by 30" rebar bears S 0 1/4°E - 57.69 feet.

Each rebar is capped with a yellow plastic cap marked "W.R. Wells, PLS 1106". A steel fence post was set by the last 3 rebar cited above, with a Bearing Object sign attached.

Nailed a Witness Corner sign to railroad tie fence post near monument.

Fences go South and West.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 8-92

Rec'd By KC

No. 92-65-C

☆ GPO-788-276