

OREGON CORNER RESTORATION FORM

Section 33,34 Township 3N
County Umatilla Date: 08/09/10

Range 29E

Corner Designation: 3N29X13

Corner common to sections 33,34 T3NR29E.

- Condition Report Only
- Not Found
- Remonumented
- Unrecorded
- Surveyed In
- Referenced Out


Previous Renewals / Surveys, etc.

Originally Surveyed by Gates. He set a post in a mound of earth in 1859.

Monuments and Accessories Found: (Condition and Source)

None.

Diagram



Sketch

Orange Magnet 22" Deep ●

Silver Magnet 23" Deep ●

○ Brass Cap 18" Deep

Blue Magnet 20" Deep ●

● Pink Magnet 22" Deep

NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N742975.33
E8538348.31

LAT - 45° 41' 49.40118" N
LON - 119° 11' 02.26421" W

Monument (s) Set (Procedures and Description)

A 1 1/2" x 30" galvanized iron pipe w/ a 2 1/2" brass cap, 18" below the surface, stamped as shown above. Set by single proportionate method.

References Set: "Deep One" magnets by Berntsen.

- An Orange magnet, 22" deep lies N 67° W, 16.33'.
- A Silver magnet, 23" deep lies N 23° E, 15.78'.
- A Pink magnet, 20" deep lies S 62°30' E, 16.57'.
- A Blue magnet, 22" deep lies S 17°20' W, 16.43'.

Location and Comments

The corner falls in an active farm field, along a N-S ridgeline, approx. 1200' E of a farm road on Piercy Farm.

Compass Declination
17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English
OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RECEIVED BY:

Date: 1-11
Rec'd By: ISE
No. 11-20-R

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055

RENEWAL DATE: 12/31/11