

OREGON CORNER RESTORATION FORM

Section 32,33 Township 3N
County Umatilla Date: 02/10/10

Range 29E

Corner Designation: 3N29X9

Corner common to Sections 32,33 T3NR29E.

_____ Condition Report Only
_____ Not Found
 Remonumented
_____ Unrecorded
_____ Surveyed In
 Referenced Out


Previous Renewals / Surveys, etc.

Originally Surveyed by David P. Thompson. He set a post in a mound of earth in 1859. Harris set a 1/2" Iron rebar, and stone, in Survey #Q-1655.


Monuments and Accessories Found: (Condition and Source)

A 1/2" Iron rebar, and stone, 12" below surface of farm field.

Diagram



Sketch



NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N742846.19
E8533034.22

LAT - 45° 41' 48.96946134" N
LON - 119° 12' 17.14915164" W

Monument (s) Set (Procedures and Description)

A 1" id x 30" Galvanized Iron pipe with a 2 1/2" Brass cap, buried 15" below surface, stamed as shown above. Rebar and stone buried alongside.

References Set:

- An orange magnet 16" deep lies N 35°30' W, 13.80'.
- A blue magnet 16" deep lies N 46°00' E, 15.17'.
- A pink magnet 16" deep lies S 38°30' E, 14.69'.
- A silver magnet 16" deep lies S 43°00' W, 14.31'.

Location and Comments

The corner is 1/2 mile West of an old farm shed on Snow Road, South app. 2.6 miles South of the intersection of Snow Road and Hwy. 320.

Compass Declination
17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English
OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RECEIVED BY:

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055

RENEWAL DATE: 12/31/11

Date: 3-10
Rec'd By: KE
No. 10-46R