

CORNER RESTORATION FORM

Township 3N Range 30E & 31E Section 1 & 6 County UMATILLA

State OREGON Date 3-11-2015 Number C-25

Corner Designation : 1/4 SECTION 1 & 6

Condition Report Only
 Not Found
 Renewed
 Surveyed In
 Referenced


Previous Renewals ORIGINAL SOURCE OF CORNER

UNDER GLO CONTRACT #81 BY D. THOMPSON DATED
JULY 8, 1859 SET POST

Accessories Found:
NONE

MONUMENT DETAIL

Found Set



BASIS OF BEARINGS, NAD 83/91 OREGON STATE PLANE COORDINATES NORTH ZONE:

NORTHING: 770510.607
 EASTING: 8585977.192

Monument & Accessories Set (Procedure and Description)

- SET 2 1/2" BRASS CAP ON 1 1/4"x30" PIPE 0.5' ABOVE GRADE IN FENCE LINE, MARKER SIGN.
- SET 5/8" REBAR & CAP PLS 61420 AT GRADE, N1°09'W 20.91', IN FENCE LINE, BEARING OBJECT SIGN.
- SET 5/8" REBAR & CAP PLS 61420 1.5' BELOW GRADE, S75°40'E 6.76'.
- SET 5/8" REBAR & CAP PLS 61420 AT GRADE, S1°48'E 29.50' IN FENCE LINE, BEARING OBJECT SIGN.
- SET 5/8" REBAR & CAP PLS 61420 1.5' BELOW GRADE, N81°08'W 19.27'.

<p style="text-align: center;"><u>Sketch of Monument, Accessories and General Area</u></p> <p style="text-align: center;"> EX. WIRE FENCE SET 5/8" REBAR & CAP PLS 61420 AT GRADE IN FENCE LINE, BEARING OBJECT SIGN SET 5/8" REBAR & CAP PLS 61420 1.5' BELOW GRADE SET 2 1/2" BRASS CAP ON 1 1/4"x30" PIPE 0.5' ABOVE GRADE IN FENCE LINE, MARKER SIGN SET 5/8" REBAR & CAP PLS 61420 AT GRADE IN FENCE LINE, BEARING OBJECT SIGN GRASSY PASTURE </p>	<div style="border: 1px solid black; padding: 5px; text-align: center;"> REGISTERED PROFESSIONAL LAND SURVEYOR </div> <div style="border: 1px solid black; padding: 5px; text-align: center;"> OREGON MAY 10, 2011 LANCE CLARK KING 61420 </div> <p style="text-align: center;">RENEWS: 6/30/2015</p> <p>Agency:</p> <p style="text-align: center;"> CK3, LLC 945 W. ORCHARD HERMISTON OREGON 97838 OFFICE: 541-567-2345 FAX: 541-567-2305 WEB: CK3LLC.NET Field Book # 0-289 </p> <div style="border: 1px solid black; padding: 5px;"> <p style="text-align: center;">COUNTY SURVEYOR RECORDING INFO</p> Received <u></u> Filed <u>6/12/2015</u> Survey No. <u>15-050-C</u> Drawing No. <u>C-853</u> Index No. <u>C-25</u> </div>
------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------