

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 4/8/15

CORNER DESIGNATION: The East One-Quarter Corner of Section 3, Township 3 North, Range 31 East, C-17.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instructions for 1/4 sec corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E  
1/4  
S3|S2  
2015  
PLS 54657

MONUMENT SET:

Re-established corner by single proportion measure, using GLO record between the Southeast and Northeast Corners of Section 3. At re-established corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with top 20" below ground, stamped as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet, buried 20" in the ground, bears North 42° East, 34.3 feet.
  - A pink deep-1 magnet, buried 20" in the ground, bears South 58° East, 41.3 feet.
  - A blue deep-1 magnet, buried 20" in the ground, bears South 35° West, 29.8 feet.
  - An orange deep-1 magnet, buried 20" in the ground, bears North 50° West, 30.0 feet.
- Buried bearing object tags with magnets.

LOCATION AND COMMENTS: Corner falls in dim East-West field berm in a CRP field.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 770667.44  
E = 8607291.21

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS  
Dean Roy

/3N31C17



15-052-C

RENEWS: 6-30-16