

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 09/17/13

CORNER DESIGNATION: 3N32, G01, The West One-Quarter Corner of Section 7.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D. S. Payne, under Contract 100, dated August, 1, 1861. Notes state: Set charred stake with mound, trench and pits as per insts. For 1/4 sec. corner. John Kimbrell, in Survey recorded in Record of Private Surveys Book 1, Page 424, indicates he found the "acknowledged 1/4 Section Corner between Sections 7 and 12" but doesn't state what was recovered.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N
R31E R32E
1/4
S12 | S7
2013
PLS 54657

MONUMENT SET: Held the intersection of proportional latitude between the West 1/4 corner of Section 6 and Southwest corner of Section 18 with a North-South field line as best remaining evidence of the original corner location. At the reestablished corner point set a reestablished corner with a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 20" below ground level, marked as shown in "Monument Marking Detail", from which:
A silver deep-1 magnet, buried 20" in ground, bears North 46 1/2° East, 39.0 feet.
A pink deep-1 magnet, buried 20" in ground, bears South 42° East, 42.6 feet.
A blue deep-1 magnet, buried 20" in ground, bears South 47 1/2° West, 33.4 feet.
An orange deep-1 magnet, buried 20" in ground, bears North 44 1/2° West, 29.2 feet.
Buried bearing object tags with magnets.

LOCATION AND COMMENTS: Corner falls in a North-South field line.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:
N= 765313.40'
E= 8617968.16'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy

\3N32G01

