

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/10/15

CORNER DESIGNATION: The West One-Quarter Corner of Section 9, Township 3 North, Range 31 East, G-9.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instrs. for 1/4 sec corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E  
1/4  
S8|S9  
2015  
PLS 54657

MONUMENT SET:

Held the projected intersection of field berms North and East as best remaining evidence of the original corner location. At re-established corner position, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with top 18" below ground level, stamped as shown in "Monument Marking Detail".

From which:

A silver deep-1 magnet buried 20" in the ground, bears North 40° East, 27.4 feet.

A pink deep-1 magnet buried 20" in the ground, bears South 47° East, 32.4 feet.

A blue deep-1 magnet buried 20" in the ground, bears South 36° East, 29.6 feet.

An orange deep-1 magnet buried 20" in the ground, bears North 53° West, 29.8 feet.

Buried bearing object tags with magnets.

LOCATION AND COMMENTS: At the projection of field berms North and East (rounded field corner), in CRP field.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 765301.41

E = 8596761.63

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS  
Dean Roy

/3N31G9

15-052-C



RENEWS: 6-30-16