

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 12/17/97

CORNER DESIGNATION: J-17, The Northwest Corner of Section 14.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was originally established by Dolphus S. Payne, Deputy Surveyor under Contract No. 100 dated August 1, 1861. Notes state: Set charred stake with mound, trench and pits as per instructions for corner to Section 10, 11, 14 and 15.

**MONUMENT MARKING DETAIL:**

T3N R31E  
S10 | S11  
S15 | S14  
1997  
PLS 1106

**MONUMENT SET:**

Survey No. Q-520-A, by LS #346, shows a location for the corner but the monument itself is not identified. After locating parcel boundary monuments set on Survey No. Q-520-A, I re-establish the position per calls on Survey No. Q-520-A.

At intersection of Cresswell Road and old fence line near an old building foundation, at position called for by LS #346 on Survey No. Q-520-A, set a 2 1/2" brass cap on a 1" x 30" iron pipe 6" below gravel road surface stamped as shown in Monument Marking Detail.

**From which:**

A brass washer stamped "PLS 1106" in South side of railroad tie 1.0 foot above ground, bears azimuth of 49°55', a distance of 26.2 feet.

A brass washer stamped "PLS 1106" in North side of UECA pole #140901, 1.0 foot above ground, bears azimuth of 90°53", a distance of 12.8 feet.

At Southeast corner of building foundation, bears azimuth of 211° 39', a distance of 143.2 feet, ("Union S.T. 92, October 1914" is stamped on the foundation).

A brass washer stamped "PLS 1106" on North side of a railroad tie 1.0 foot above ground, bears azimuth of 269°52', a distance of 27.0 feet.

Both railroad ties and power pole have bearing object signs attached.

**LOCATION AND COMMENTS:**

Azimuths are measured from true North.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: William R. Wells, PLS  
Jason Wells

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will. R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-98*

**RECEIVED BY**

Umatilla County Surveyor

Date 12-97

Rec'd By AK

No. 97-247-B