

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/9/15

CORNER DESIGNATION: The West One-Quarter Corner of Section 13, Township 3 North, Range 31 East, L-21.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instrs. for 1/4 sec corner. John Kimbrell called an East-West fence line as the undisputed line through the center of Sections 13 and 14 in his 1900 survey recorded in Private Survey Book 1, Page 424 and 425. Kimbrell does not indicate he found a corner monument.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
1/4
S14 | S13
2015
PLS 54657

MONUMENT SET:

There are no fence or field lines East-West remaining at the corner point. The corner falls in a North-South field berm. Re-established corner by single proportion measure between the Southwest and Northwest corners of Section 13 and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with top 20" below ground level, stamped as shown in "Monument Marking Detail".

From which:

A silver deep-1 magnet, buried 20" in the ground, bears North 45° East, 32.8 feet.

A pink deep-1 magnet, buried 20" in the ground, bears South 47° East, 38.2 feet.

A blue deep-1 magnet, buried 20" in the ground, bears South 34° West, 35.9 feet.

An orange deep-1 magnet, buried 20" in the ground, bears North 34° West, 36.6 feet.

Buried bearing object tags with magnets. Set steel fence post with witness sign 1 foot North of monument.

LOCATION AND COMMENTS: At a calculated point in North/South field berm.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 760002.78

E = 8612747.35

FIRM: Wells Surveying

P.O. Box 1696

Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS

Dean Roy

/3N31L21



RENEWS: 6-30-16

15-052-C