

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/07/06

CORNER DESIGNATION: 3N31, N-21, The Northeast Corner of Section 23.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for corner to Secs. 13 & 14, 23 & 24. John Kimbrell, in survey recorded in Book 1, Page 424, calls the corner in a East-West road and set a stake. Kimbrells notes indicate the parties involved with the survey would later set a stone at the corner point.

MONUMENT AND ACCESSORIES FOUND: None. Held the intersection of the visual centerline of Howdysshell road running East-West, and a field berm extending North as the best remaining evidence of the original corner position.

MONUMENT MARKING DETAIL:

T3N R31E
S14|S13
S23|S24
2006
PLS 1106

MONUMENT SET:

At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 10" below gravel road surface. Monument marked as shown in monument marking detail.

From which:

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 43° East, 17.8 feet. Set steel fence post with witness sign attached by this accessory.

A blue Deep-1 magnet buried 22" below ground level bears South 34° East, 35.2 feet.

A purple Deep-1 magnet buried 22" below ground level bears South 36 1/2° West, 34.0 feet.

An orange Deep-1 magnet buried 22" below ground level bears North 51° West, 31.1 feet.

Attached bearing object sign to rebar accessory and buried signs with magnets.

LOCATION AND COMMENTS: Corner is located at the intersection of the centerline of Howdysshell road running East-West, and a field berm extending North.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 757385.50
E = 8612770.50

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31N21

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08